



US007713615B2

(12) **United States Patent**  
**Black et al.**

(10) **Patent No.:** **US 7,713,615 B2**  
(45) **Date of Patent:** **May 11, 2010**

(54) **REINFORCED FIBER CEMENT ARTICLE AND METHODS OF MAKING AND INSTALLING THE SAME**

815,801 A 3/1906 Depew et al.  
1,399,023 A 12/1921 Murray

(75) Inventors: **Andrew J. Black**, Rancho Cucamonga, CA (US); **Weiling Peng**, Alta Loma, CA (US)

(Continued)

(73) Assignee: **James Hardie International Finance B.V.**, Amsterdam (NL)

FOREIGN PATENT DOCUMENTS

AU 515151 3/1981

(\* ) Notice: Subject to any disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 204 days.

(Continued)

(21) Appl. No.: **10/117,401**

OTHER PUBLICATIONS

(22) Filed: **Apr. 3, 2002**

International Search Report for PCT/US 02/10760 dated Aug. 5, 2002.

(65) **Prior Publication Data**

US 2003/0054123 A1 Mar. 20, 2003

(Continued)

**Related U.S. Application Data**

*Primary Examiner*—Michael C Miggins  
(74) *Attorney, Agent, or Firm*—Gardere Wynne Sewell LLP

(60) Provisional application No. 60/281,195, filed on Apr. 3, 2001.

(57) **ABSTRACT**

(51) **Int. Cl.**  
**B32B 13/02** (2006.01)  
**B32B 13/10** (2006.01)

(52) **U.S. Cl.** ..... **428/294.7**; 428/113; 53/294; 53/781.5; 53/518

(58) **Field of Classification Search** ..... 428/294.7, 428/105, 221, 327, 113; 52/309.7, 518, 536, 52/520, 546, 552, 274, 296, 781.5, 721.1  
See application file for complete search history.


In one embodiment, a reinforced fiber cement article comprising a fiber cement piece and a reinforcing fixture bonded to a portion of the fiber cement piece for improving the performance, strength and durability of the fiber cement piece. The reinforcing fiber cement article could be used as or in conjunction with a siding plank assembly, which further comprises an interlocking feature that allows the siding plank to be stacked with other siding planks in a manner such that a uniform and deep shadow line is created. The interlocking feature sets the gauge of the exposed plank face and allows for leveling of the plank during installation. The reinforcing fixture could also serve as a thick butt piece or a plastic spline that produces a deep shadow line. A cementitious adhesive is used to bond the reinforcing fixture to the fiber cement piece.

(56) **References Cited**

U.S. PATENT DOCUMENTS

369,216 A 8/1887 Temple  
494,763 A 4/1893 Smidth  
525,442 A 9/1894 Burrows  
575,074 A 1/1897 Smith  
774,114 A 11/1904 Spear

**31 Claims, 69 Drawing Sheets**



U.S. PATENT DOCUMENTS					
1,510,497 A	10/1924	C.L. Keller	3,902,911 A	9/1975	Messenger
1,630,801 A	5/1927	Parsons ..... 264/33	3,921,346 A	11/1975	Sauer et al.
1,634,809 A	7/1927	Weiss	3,928,701 A	12/1975	Roehner
1,698,557 A	1/1929	O'Brien ..... 52/426	3,974,024 A	8/1976	Yano et al.
1,856,932 A	5/1932	Shaw	3,986,312 A	10/1976	Calhoun et al. .... 52/242
1,856,936 A	5/1932	Turner	3,992,845 A	11/1976	Grzesiek et al.
1,871,843 A	8/1932	Ericson	4,010,587 A	3/1977	Larsen
1,930,024 A	10/1933	Varden	4,010,589 A	3/1977	Gross
1,943,663 A	1/1934	Ericson	4,015,392 A	4/1977	Eaton
1,959,519 A	5/1934	Black	4,028,859 A	6/1977	Bellagamba ..... 52/393
1,976,984 A	10/1934	Condon et al.	4,034,528 A	7/1977	Sanders et al.
1,978,519 A	10/1934	Willcock et al.	4,047,355 A	9/1977	Knorr
1,995,393 A	3/1935	Manske	4,052,829 A	10/1977	Chapman ..... 52/281
1,997,939 A	4/1935	Loucks ..... 52/506.08	4,058,944 A	11/1977	Rieger et al. .... 52/235
2,009,619 A	7/1935	Hashberger	4,063,393 A	12/1977	Toti ..... 52/245
2,062,149 A	11/1936	Stark et al.	4,065,899 A	1/1978	Kirkhuff
2,182,372 A	12/1939	Cox et al.	4,070,843 A	1/1978	Leggiere et al.
2,224,351 A	12/1940	Kaye	4,076,884 A	2/1978	Riley et al.
2,253,753 A	8/1941	Black	4,079,562 A	3/1978	Englert et al.
2,276,170 A	3/1942	Elmendorf	1,512,084 A	5/1978	Arthur et al.
2,317,634 A	4/1943	Olsen et al.	4,101,335 A	7/1978	Barrable
2,323,230 A	6/1943	McAvoy	4,102,106 A	7/1978	Golder et al.
2,324,325 A	7/1943	Schuh	4,104,103 A	8/1978	Tarullo
2,354,639 A	7/1944	Seymour	4,104,840 A	8/1978	Heintz et al.
2,400,357 A	5/1946	Krajci	4,110,507 A	8/1978	Colledge
2,413,794 A	1/1947	Small	4,112,647 A	9/1978	Scheid
2,447,275 A	8/1948	Price	4,118,236 A	10/1978	Erskine
2,511,083 A	6/1950	Small	4,128,696 A	12/1978	Goebel et al.
2,517,122 A	8/1950	Lockwood	4,132,555 A	1/1979	Barrable
2,624,298 A	1/1953	Farren	4,150,517 A	4/1979	Warner, Sr. .... 52/288.1
2,694,025 A	11/1954	Slyater et al.	4,152,878 A	5/1979	Balinski
2,724,872 A	11/1955	Herbes	4,166,749 A	9/1979	Sterrett et al.
2,782,463 A	2/1957	Bergvall et al. .... 52/264	4,183,188 A	1/1980	Goldsby
2,928,143 A	3/1960	Newton	4,187,658 A	2/1980	Reinwall, Jr.
3,046,700 A	7/1962	Davenport	4,203,788 A	5/1980	Clear
3,047,985 A	8/1962	Murphy	4,211,525 A	7/1980	Vetter et al. .... 425/326.1
3,173,229 A	3/1965	Weber	4,222,785 A	9/1980	Henderson
3,181,662 A	5/1965	Maertzig, Jr.	4,231,573 A	11/1980	Kelly
3,214,876 A	11/1965	Mattes	4,268,317 A	5/1981	Rayl
3,235,039 A	2/1966	O'Donnell	4,274,239 A	6/1981	Carroll
3,236,932 A	2/1966	Grigas et al. .... 52/543	4,292,364 A *	9/1981	Wesch et al. .... 428/286
3,274,743 A	9/1966	Blum, Jr.	4,298,647 A	11/1981	Cancio et al.
3,284,980 A	11/1966	Dinkel	4,307,551 A	12/1981	Crandell ..... 52/235
3,333,379 A	8/1967	Harris ..... 52/364	4,321,780 A	3/1982	Hooper et al. .... 52/461
3,408,786 A	11/1968	Snyker	4,327,528 A	5/1982	Fritz
3,415,019 A	12/1968	Andersen ..... 52/94	4,337,290 A	6/1982	Kelly et al.
3,416,275 A	12/1968	Van Loghem at al.	4,339,489 A	7/1982	Barker et al.
3,421,281 A	1/1969	Harris ..... 52/733.3	4,343,127 A	8/1982	Greve et al.
3,481,093 A	12/1969	Davidson ..... 52/293.1	4,361,616 A	11/1982	Bomers
3,527,004 A	9/1970	Sorenson	4,362,566 A	12/1982	Hinterwaldner
3,606,720 A	9/1971	Cookson ..... 52/714	4,366,657 A	1/1983	Hopman ..... 52/405.1
3,625,808 A *	12/1971	Martin ..... 161/37	4,370,166 A	1/1983	Powers et al.
3,635,742 A	1/1972	Fujimasu	4,373,955 A	2/1983	Bouchard et al.
3,660,955 A	5/1972	Simon	4,373,957 A	2/1983	Pedersen et al. .... 106/711
3,663,341 A	5/1972	Veneziale, Jr.	4,377,977 A	3/1983	Wurster
3,663,353 A	5/1972	Long et al.	4,379,553 A	4/1983	Kelly
3,703,795 A	11/1972	Mattes	4,380,564 A	4/1983	Cancio et al.
3,708,943 A	1/1973	Thomas et al. .... 52/309.8	4,392,336 A	7/1983	Gansle
3,729,368 A	4/1973	Ingham et al.	4,399,643 A	8/1983	Hafner
3,754,365 A	8/1973	Carrick et al.	4,406,703 A	9/1983	Guthrie et al.
3,780,483 A	12/1973	Mattes	4,420,351 A	12/1983	Lussi et al.
3,782,985 A	1/1974	Gebhardt	4,424,261 A	1/1984	Keeling et al.
3,797,179 A	3/1974	Jackson	4,429,214 A	1/1984	Brindley et al.
3,797,190 A	3/1974	Widdowson	4,441,944 A	4/1984	Massey
3,804,058 A	4/1974	Messenger	4,442,219 A	4/1984	TenEyck et al.
3,818,668 A	6/1974	Chamiga	4,462,730 A	7/1984	Knohl ..... 411/371.1
3,835,604 A	9/1974	Hoffman, Jr.	4,462,835 A	7/1984	Car
3,847,633 A	11/1974	Race	4,463,532 A	8/1984	Faw
3,866,378 A	2/1975	Kessler	4,465,729 A	8/1984	Cancio et al.
3,869,295 A	3/1975	Bowles et al. .... 521/55	4,501,830 A	2/1985	Miller et al.
3,888,617 A	6/1975	Barnett ..... 425/296	4,502,256 A	3/1985	Hahn et al. .... 52/63
			4,504,320 A	3/1985	Rizer et al.
			4,506,486 A	3/1985	Culpepper, Jr. et al.

4,514,947 A	5/1985	Grail	5,210,989 A	5/1993	Jakel
4,553,366 A	11/1985	Guerin	5,224,318 A	7/1993	Kemerer
4,559,894 A	12/1985	Thompson	5,226,274 A	7/1993	Sommerstein
4,586,304 A	5/1986	Flammand	5,229,437 A	7/1993	Knight
4,588,443 A	5/1986	Bache	5,234,754 A	8/1993	Bache
4,592,185 A	6/1986	Lynch et al.	D339,642 S	9/1993	Blazley et al. .... D25/119
4,626,398 A	12/1986	Vetter et al. .... 264/566	5,242,736 A	9/1993	Van Erden et al. .... 428/137
4,637,860 A	1/1987	Harper	5,245,811 A	9/1993	Knorr
4,640,715 A	2/1987	Heitzmann et al.	5,247,773 A	9/1993	Weir
4,641,469 A	2/1987	Wood	5,252,526 A	10/1993	Whittemore
4,642,137 A	2/1987	Heitzmann et al.	5,259,872 A	11/1993	Shinozaki et al.
4,661,398 A	4/1987	Ellis	5,268,226 A	12/1993	Sweeney
4,670,079 A	6/1987	Thompson	5,282,317 A	2/1994	Carter et al.
4,673,659 A	6/1987	Wood et al.	5,297,370 A	3/1994	Greenstreet et al. .... 52/287.1
4,680,059 A	7/1987	Cook et al.	5,301,484 A	4/1994	Jansson
4,685,263 A	8/1987	Ting ..... 52/235	5,305,568 A	4/1994	Beckerman
4,698,942 A	10/1987	Swartz	5,305,577 A	4/1994	Richards et al.
4,730,398 A	3/1988	Stanton	5,319,909 A	6/1994	Singleterry
4,737,191 A	4/1988	Meynardi	5,323,581 A *	6/1994	Jakel ..... 52/519
4,748,771 A	6/1988	Lehnert et al.	5,330,573 A	7/1994	Nakano et al.
4,779,313 A	10/1988	Gonas ..... 24/289	5,334,242 A	8/1994	O'Toole
4,780,141 A	10/1988	Double et al.	5,338,349 A	8/1994	Farrar
4,789,604 A	12/1988	van der Hoeven	5,349,802 A	9/1994	Kariniemi
4,793,861 A	12/1988	Sohm	5,352,288 A	10/1994	Mallow
4,803,105 A	2/1989	Kretow et al.	5,352,290 A	10/1994	Takeshita et al.
4,808,229 A	2/1989	Arhelger	5,358,676 A	10/1994	Jennings et al.
4,811,538 A	3/1989	Lehnert et al.	5,369,924 A	12/1994	Neudorf et al. .... 52/235
4,827,621 A	5/1989	Borsuk	5,372,678 A	12/1994	Sagstetter et al.
4,840,672 A	6/1989	Baes	5,378,279 A	1/1995	Conroy
4,841,702 A	6/1989	Huettemann	5,391,245 A	2/1995	Turner
4,842,649 A	6/1989	Heitzmann et al.	5,394,672 A	3/1995	Seem
4,854,101 A	8/1989	Champagne	5,395,685 A	3/1995	Seth et al.
4,858,402 A	8/1989	Putz	5,397,631 A	3/1995	Green et al. .... 428/219
4,866,896 A	9/1989	Shreiner et al. .... 52/235	5,410,852 A	5/1995	Edgar et al.
4,870,788 A	10/1989	Hassan	5,425,985 A	6/1995	Irvin
4,876,827 A	10/1989	Williams et al. .... 52/12	5,425,986 A	6/1995	Guyette
4,895,598 A	1/1990	Hedberg et al. .... 106/694	5,428,931 A	7/1995	Ragsdale
4,906,408 A	3/1990	Bouniol	5,437,934 A	8/1995	Witt et al. .... 428/537.1
4,914,885 A	4/1990	Baker et al. .... 52/520	5,443,603 A	8/1995	Kirkendall
4,924,644 A	5/1990	Lewis	5,461,839 A	10/1995	Beck
4,927,696 A	5/1990	Berg	5,465,547 A	11/1995	Jakel
4,930,287 A	6/1990	Volk et al.	5,475,961 A	12/1995	Menchetti
4,937,993 A	7/1990	Hitchins	5,477,617 A	12/1995	Guy
4,952,631 A	8/1990	McAlpin et al.	5,482,550 A	1/1996	Strait
4,955,169 A	9/1990	Shisko	5,501,050 A	3/1996	Ruel
4,963,430 A	10/1990	Kish et al. .... 428/220	5,511,316 A	4/1996	Fischer et al.
4,969,250 A	11/1990	Hickman et al. .... 29/521	5,517,795 A	5/1996	Doke ..... 52/36.4
4,969,302 A	11/1990	Coggan et al.	5,522,926 A	6/1996	Richard et al.
4,975,396 A	12/1990	Thiery	5,526,627 A	6/1996	Beck
4,985,119 A	1/1991	Vinson et al.	5,531,824 A	7/1996	Burkes et al.
4,995,605 A	2/1991	Conville	5,545,297 A	8/1996	Andersen et al.
4,999,056 A	3/1991	Rasmussen	5,557,903 A	9/1996	Haddock ..... 52/508
5,017,232 A	5/1991	Miceli	5,561,173 A	10/1996	Dry
5,022,207 A	6/1991	Hartnett	5,564,233 A	10/1996	Norton ..... 52/60
5,045,378 A	9/1991	Libby	5,564,245 A	10/1996	Rademacher
5,047,086 A	9/1991	Hayakawa et al.	5,565,026 A	10/1996	Hense et al.
5,067,675 A	11/1991	Brant et al. .... 248/48.2	5,580,378 A	12/1996	Shulman
D322,678 S	12/1991	Brathwaite et al. .... D25/136	5,580,409 A	12/1996	Andersen et al.
5,076,986 A	12/1991	Delvaux et al.	5,598,671 A	2/1997	Ting ..... 52/235
5,077,952 A	1/1992	Moure	5,603,758 A	2/1997	Schreifels, Jr. et al.
5,080,022 A	1/1992	Carlson	5,617,690 A	4/1997	Gibbs
5,106,557 A	4/1992	Rirsch et al.	5,622,556 A	4/1997	Shulman ..... 106/677
5,108,679 A	4/1992	Rirsch et al.	5,631,097 A	5/1997	Andersen et al.
5,112,405 A	5/1992	Sanchez	5,634,314 A	6/1997	Champagne
5,114,617 A	5/1992	Smetana et al.	5,648,144 A	7/1997	Maurer et al.
5,115,621 A	5/1992	Kobayashi	5,651,227 A	7/1997	Anderson
5,117,600 A	6/1992	Yerushalmi et al. .... 52/262	5,661,939 A	9/1997	Coulis et al.
5,143,780 A	9/1992	Balassa	5,673,489 A	10/1997	Robell
5,155,958 A	10/1992	Huff ..... 52/235	5,673,529 A	10/1997	Treister et al.
5,167,710 A	12/1992	Leroux et al.	5,675,955 A	10/1997	Champagne
5,177,305 A	1/1993	Pichat	5,692,345 A	12/1997	Mogaki et al. .... 52/483.1
5,198,052 A	3/1993	Ali	5,694,727 A	12/1997	Dobija
5,198,275 A	3/1993	Klein	5,697,189 A	12/1997	Miller et al.

# US 7,713,615 B2

D388,884 S	1/1998	Karnoski .....	D25/102	6,319,456 B1	11/2001	Gilbert et al.	
5,714,002 A	2/1998	Styron		6,324,807 B1	12/2001	Ishiko	
5,718,758 A	2/1998	Breslauer		6,346,146 B1	2/2002	Duselis et al.	
5,718,759 A	2/1998	Stav et al.		6,357,193 B1	3/2002	Morris .....	52/553
5,724,783 A	3/1998	Mandish .....	52/745.05	6,365,081 B1	4/2002	Beck	
5,725,652 A	3/1998	Shulman		6,367,208 B1	4/2002	Campbell et al.	
5,729,946 A	3/1998	Beck		6,367,220 B1	4/2002	Krause et al.	
5,732,520 A	3/1998	Maietta .....	52/483.1	6,415,574 B2	7/2002	Beck	
5,735,092 A	4/1998	Clayton et al.		6,421,973 B1	7/2002	Gregg et al.	
5,736,594 A	4/1998	Boles et al. ....	524/2	6,423,167 B1	7/2002	Palmer et al.	
5,741,844 A	4/1998	Nass et al.		6,425,218 B1	7/2002	Doyon et al.	
5,743,056 A	4/1998	Balla-Goddard et al.		6,430,885 B1	8/2002	Ito et al. ....	52/483.1
5,749,187 A	5/1998	Umehara et al.		6,488,792 B2 *	12/2002	Mathieu .....	156/40
5,768,841 A	6/1998	Swartz et al.		6,510,667 B1	1/2003	Cottier et al. ....	52/742.14
5,791,109 A	8/1998	Lehnert et al.		6,514,624 B2	2/2003	Takemoto	
5,802,790 A	9/1998	Lamont et al. ....	52/288.1	6,516,580 B1	2/2003	Maietta .....	52/483.1
5,817,262 A	10/1998	Englert et al.		6,526,717 B2	3/2003	Waggoner et al.	
5,842,280 A	12/1998	Robell		6,539,643 B1	4/2003	Gleeson	
5,848,508 A	12/1998	Albrecht		6,550,203 B1	4/2003	Little	
5,848,509 A	12/1998	Knapp et al.		6,550,210 B1	4/2003	Levine et al.	
5,857,303 A	1/1999	Beck et al.		6,551,694 B1	4/2003	Imamichi et al.	
5,878,543 A	3/1999	Mowery		6,562,444 B1	5/2003	Gleeson et al.	
5,887,403 A	3/1999	Beck		6,572,697 B2	6/2003	Gleeson et al. ....	106/705
5,891,374 A	4/1999	Shah et al.		6,610,358 B1	8/2003	Williams et al.	
5,916,095 A *	6/1999	Tamlyn .....	52/58	6,626,947 B2	9/2003	Lester et al. ....	623/22.23
5,924,213 A	7/1999	Lee		6,676,745 B2	1/2004	Merkley et al.	
5,928,777 A	7/1999	Cox et al.		6,679,011 B2	1/2004	Beck et al.	
5,935,699 A	8/1999	Barber		6,689,451 B1	2/2004	Peng et al.	
5,945,208 A	8/1999	Richards et al.		6,699,576 B2	3/2004	Peng et al. ....	428/294.7
5,946,870 A	9/1999	Bifano et al. ....	52/254	D489,137 S	4/2004	Eichner et al. ....	D25/119
5,946,876 A	9/1999	Grace, Sr. et al.		D489,463 S	5/2004	Barnett .....	D25/119
5,950,319 A	9/1999	Harris		6,737,008 B2	5/2004	Gilbert et al.	
5,968,257 A	10/1999	Ahrens		D492,424 S	6/2004	Barnett .....	D25/119
5,979,135 A	11/1999	Reeves		6,760,978 B2	7/2004	Gleeson	
5,987,838 A	11/1999	Beck		6,901,713 B2	6/2005	Axsom	
6,000,185 A	12/1999	Beck et al.		6,913,819 B2	7/2005	Wallner	
6,012,255 A	1/2000	Smid et al.		6,941,720 B2	9/2005	DeFord et al.	
6,018,924 A	2/2000	Tamlyn .....	52/716.8	7,028,436 B2	4/2006	Bezubic, Jr. ....	52/288.1
6,026,616 A	2/2000	Gibson .....	52/95	7,089,709 B2	8/2006	Waggoner	
6,029,415 A	2/2000	Culpepper et al.		7,191,570 B1	3/2007	Eaton et al. ....	52/506.09
6,030,447 A	2/2000	Najie et al.		7,325,325 B2	2/2008	Gleeson .....	33/563
6,046,269 A	4/2000	Nass et al.		2001/0047741 A1	12/2001	Gleeson et al. ....	106/709
6,049,987 A	4/2000	Robell		2002/0100249 A1	8/2002	Peng et al.	
6,055,787 A	5/2000	Gerhaher et al.		2002/0139082 A1	10/2002	DeFord et al.	
6,063,856 A	5/2000	Mass		2003/0046891 A1	3/2003	Colada et al.	
6,079,175 A	6/2000	Clear		2003/0054123 A1	3/2003	Black et al.	
6,084,011 A	7/2000	Lucero et al.		2003/0056458 A1	3/2003	Black et al.	
6,093,473 A	7/2000	Min		2003/0089061 A1	5/2003	DeFord et al.	
6,110,525 A	8/2000	Stoddard .....	427/154	2003/0172606 A1	9/2003	Anderson .....	52/302.1
6,122,876 A	9/2000	Bado et al.		2003/0200721 A1	10/2003	Gleeson et al.	
6,122,877 A	9/2000	Hendrickson et al.		2004/0103610 A1	6/2004	Axsom	
6,134,855 A	10/2000	Beck		2004/0163331 A1	8/2004	Peng et al.	
6,138,430 A	10/2000	Van Acoleyen et al.		2005/0000172 A1	1/2005	Anderson .....	52/198
6,139,620 A	10/2000	Suzuki et al.		2005/0138865 A1	6/2005	Gleeson et al.	
6,145,255 A	11/2000	Allaster .....	52/95	2005/0210790 A1	9/2005	Wallner	
6,161,353 A	12/2000	Negola et al.		2005/0262799 A1	12/2005	Gleeson et al.	
6,161,354 A	12/2000	Gilbert et al.		2005/0284339 A1	12/2005	Brunton et al.	
6,164,032 A	12/2000	Beck		2006/0010800 A1	1/2006	Bezubic, Jr.	
6,164,214 A	12/2000	Smorgon et al.		2008/0022627 A1	1/2008	Gleeson	
6,170,212 B1	1/2001	Suchyna et al.		2008/0104918 A1	5/2008	Gleeson	
6,170,214 B1	1/2001	Treister et al.		2008/0163582 A1	7/2008	Trevethick	
6,170,215 B1	1/2001	Nasi					
6,176,920 B1	1/2001	Murphy et al.					
6,195,952 B1	3/2001	Culpepper et al.					
6,226,947 B1	5/2001	Bado et al.		AU	70389	10/1981	
6,276,107 B1	8/2001	Waggoner et al.		AU	8858982	3/1983	
6,277,189 B1	8/2001	Chugh		AU	84015-82	12/1983	
6,290,769 B1	9/2001	Carkner		AU	94035 S	11/1986	
6,295,777 B1	10/2001	Hunter et al.		AU	95878 S	3/1987	
6,298,626 B2	10/2001	Rudden		AU	98800 S	12/1987	
6,308,486 B1	10/2001	Medland et al. ....	52/506.05	AU	99683 S	2/1988	
6,315,489 B1	11/2001	Watanabe		AU	102662 S	1/1989	
6,316,087 B1 *	11/2001	Lehan .....	428/294.7	AU	103840 S	5/1989	

## FOREIGN PATENT DOCUMENTS

# US 7,713,615 B2

AU	104552 S	8/1989	DE	4104919	8/1992
AU	108078 S	7/1990	DE	4209834	9/1993
AU	616088	7/1990	DE	4228338	10/1993
AU	4687889	7/1990	DE	9403018.9	5/1994
AU	110320 S	2/1991	DE	19858342	12/1998
AU	7620191	6/1992	DE	20006112	7/2000
AU	117138 S	5/1993	DE	19549535	1/2001
AU	118448 S	10/1993	EP	1086311	10/1967
AU	118862 S	11/1993	EP	0055504	7/1982
AU	686135	11/1994	EP	0103097	3/1984
AU	677649	12/1994	EP	0173553	3/1986
AU	122634 S	2/1995	EP	0184477	6/1986
AU	123141 S	4/1995	EP	0222339	5/1987
AU	123142 S	4/1995	EP	0305209	3/1989
AU	681049	9/1996	EP	0347092	12/1989
AU	702630	11/1996	EP	0220073	5/1991
AU	130941 S	8/1997	EP	0428431	5/1991
AU	132812 S	2/1998	EP	0430667	6/1991
AU	732998	5/1998	EP	0482810	4/1992
AU	135097 S	9/1998	EP	484 283 A1	6/1992
AU	135557 S	11/1998	EP	0558239	9/1993
AU	137291 S	5/1999	EP	0564447	10/1993
AU	199886116	5/1999	EP	0625618	11/1994
AU	137791 S	7/1999	EP	0683282	11/1995
AU	19952711	3/2000	EP	0708213	4/1996
AU	140607 S	5/2000	FR	990 242	9/1951
AU	20078733	5/2001	FR	2248246	5/1975
AU	200078733	5/2001	FR	2405908	5/1979
AU	0121275	6/2001	FR	2540160	8/1984
AU	783430	6/2001	FR	2562591	10/1984
AU	200072012	6/2001	FR	2562591	10/1985
AU	735352	7/2001	FR	2 624 870	12/1987
AU	20053659	3/2002	FR	2624870	6/1989
AU	147568 S	4/2002	FR	2628775	9/1989
AU	2001287356	4/2002	FR	2702790	9/1994
AU	148485 S	7/2002	GB	119182	9/1918
AU	2002301511	6/2003	GB	558239	12/1943
AU	2003204739	7/2003	GB	558584	1/1944
AU	152915 S	8/2003	GB	564447	9/1944
AU	153491 S	10/2003	GB	1086311	10/1967
AU	153493 S	10/2003	GB	1125825	9/1968
AU	153494 S	10/2003	GB	1174902	12/1969
AU	153495 S	10/2003	GB	1269357	4/1972
AU	153496 S	10/2003	GB	1512084	5/1978
AU	2003204418	12/2003	GB	2021186	11/1979
AU	2003238481	12/2003	GB	2041384	9/1980
AU	2003257906	7/2004	GB	1577648	10/1980
AU	2004200339	6/2005	GB	2064989	6/1981
CA	730345	3/1966	GB	2 067 622	7/1981
CA	1084230	8/1980	GB	2075079	11/1981
CA	2313456	6/2000	GB	2 078 611	1/1982
CH	368918	4/1963	GB	2080851	2/1982
CH	606674	11/1978	GB	2083512	3/1982
CH	678882	11/1991	GB	2148871	6/1985
CH	684285	8/1994	GB	2199857	7/1988
CH	684287 A5	8/1994	GB	2 252 987	8/1992
CL	654-02	4/2001	GB	2340071	2/2000
CN	1081168 A	1/1994	JP	49-46761	12/1971
CN	2281378 Y	5/1998	JP	49-116445	2/1973
CN	2281378 Y	5/1998	JP	49-46761	12/1974
DE	1952082	4/1971	JP	51-23229	6/1976
DE	2460879	6/1976	JP	52051719	4/1977
DE	2460880	6/1976	JP	53050229	5/1978
DE	2610998	9/1977	JP	54-123129	9/1979
DE	3210326	9/1983	JP	56-130832	3/1980
DE	3232106	3/1984	JP	55-116684	9/1980
DE	3505335	8/1986	JP	5252429	9/1980
DE	3621010	1/1988	JP	56-048413	5/1981
DE	3932176	6/1990	JP	57-15641	9/1982
DE	3923800	1/1991	JP	57-156541	9/1982
DE	40 04 103	8/1991	JP	5641881	9/1982
DE	4004103	8/1991	JP	58045008	3/1983
DE	4004103 A	8/1991	JP	58059803	4/1983

## US 7,713,615 B2

Page 6

JP	60-105715	7/1985	JP	2002097732	4/2002
JP	58202823	7/1985	JP	2002161623	6/2002
JP	60-242242	12/1985	JP	2002354091	12/2002
JP	61-68967	4/1986	JP	2002364091	12/2002
JP	03744/1987	2/1987	JP	2004027497	1/2004
JP	037444	2/1987	KR	19928773	10/1992
JP	63-19636	2/1988	KR	1019967005677 A	11/1996
JP	63 31426	6/1988	KR	200158855 Y1	5/1998
JP	63257631	10/1988	KR	100231910 B1	9/1999
JP	63-47229	12/1988	KR	200172372 Y1	12/1999
JP	64-020910	1/1989	KR	100274218 B1	9/2000
JP	64-022385	1/1989	MY	107883	6/1996
JP	64-025200	1/1989	NO	9901129	9/2000
JP	6420910	1/1989	NZ	19354	11/1984
JP	6422385	1/1989	NZ	20119	10/1985
JP	6425200	1/1989	NZ	20120	10/1985
JP	64-50541	3/1989	NZ	20844	11/1986
JP	01128748	5/1989	NZ	210395	8/1987
JP	1178658	7/1989	NZ	211265	1/1989
JP	02192447	7/1990	NZ	22705	7/1989
JP	2204566	8/1990	NZ	247463	8/1989
JP	02-236350	9/1990	NZ	218315	5/1990
JP	3-4654	2/1991	NZ	221389	12/1991
JP	3-63641	6/1991	NZ	25267	6/1993
JP	3-66338	6/1991	NZ	230209	12/1993
JP	04089340	3/1992	NZ	26065	7/1994
JP	4149352	5/1992	NZ	26066	7/1994
JP	09-193120	7/1992	NZ	25838	11/1994
JP	04295072	10/1992	NZ	240533	7/1996
JP	04300232	10/1992	NZ	270310	12/1996
JP	5-1532	1/1993	NZ	280409	6/1997
JP	05-044323	2/1993	NZ	280235	9/1997
JP	058215	2/1993	NZ	259493	10/1997
JP	565760	3/1993	NZ	248942	11/1997
JP	542192	10/1993	NZ	242960	12/1997
JP	06-017621	1/1994	NZ	306382	2/1998
JP	6023889	2/1994	NZ	21875	4/1998
JP	06-080264	3/1994	NZ	314544	6/1998
JP	06123158 A	5/1994	NZ	331553	1/2000
JP	6-28563	8/1994	NZ	336159	3/2000
JP	06278116	10/1994	NZ	334899	4/2000
JP	08012450	1/1996	NZ	400643	4/2000
JP	08068184	3/1996	NZ	334918	8/2000
JP	08074377	3/1996	NZ	335529	12/2000
JP	2507028	5/1996	NZ	508055	12/2000
JP	08-175859	7/1996	NZ	502017	1/2001
JP	08217561	8/1996	NZ	331336	4/2001
JP	2538120	3/1997	NZ	500215	6/2001
JP	09-123340	5/1997	NZ	507846	4/2002
JP	2538120	6/1997	NZ	502004	8/2002
JP	09-296560	11/1997	NZ	505799	2/2003
JP	10025841	1/1998	NZ	504881	3/2003
JP	10046741	2/1998	NZ	512028	7/2003
JP	10-121693	5/1998	NZ	516912	7/2003
JP	10-245925	9/1998	NZ	524520	9/2003
JP	63117939	12/1998	NZ	518988	10/2003
JP	11-210203	8/1999	NZ	517658	11/2003
JP	11-217918	8/1999	NZ	521491	6/2004
JP	11-511110	9/1999	NZ	525507	9/2004
JP	11241448	9/1999	NZ	525328	2/2005
JP	11247307	9/1999	NZ	528304	4/2005
JP	11256683	9/1999	NZ	530605	6/2005
JP	11-280172	10/1999	NZ	532182	12/2005
JP	2000-008581	1/2000	NZ	536129	2/2006
JP	2000008581	1/2000	NZ	542948	2/2006
JP	2000-043196	2/2000	NZ	520286	7/2006
JP	2000064554	2/2000	PL	106840	1/1999
JP	2000-110272	4/2000	PL	339671	1/2001
JP	2000154612	6/2000	SG	93908341	4/1987
JP	2000179104	6/2000	SG	92906122	8/1989
JP	2000-302522	10/2000	SG	97920847	11/1990
JP	2001336230	12/2001	SG	97912869	4/1993
JP	2002047750	2/2002	SG	95012084	1/1994

SG	96026257	4/1994
SG	96120035	4/1995
SG	97059547	5/1996
SG	98021017	9/1996
SG	98021751	9/1996
SG	98051485	2/1997
SG	97018402	5/1997
SG	98012917	6/1997
SG	99017030	10/1997
SU	587123	1/1978
SU	607813	4/1978
SU	655678	4/1979
SU	1114646	9/1984
SU	1606633	11/1990
TW	282800	9/1986
TW	278537	6/1996
TW	282800	12/2005
TW	255851	6/2006
TW	278536	4/2007
WO	8102758	10/1981
WO	8503966	9/1985
WO	9008240	7/1990
WO	9111321	8/1991
WO	9114057	9/1991
WO	WO 92/17657	10/1992
WO	9306316	4/1993
WO	9312303	6/1993
WO	WO 93/21126	10/1993
WO	9324711	12/1993
WO	9419561	9/1994
WO	95/26450	* 10/1995
WO	9614482	3/1996
WO	9614482	5/1996
WO	WO 97/07968	3/1997
WO	WO 97/08111	3/1997
WO	WO 97/08401	3/1997
WO	WO 97/23696	7/1997
WO	9728342	8/1997
WO	WO 98/10151	* 3/1998
WO	9816697	4/1998
WO	9832713	7/1998
WO	WO 98/45222	10/1998
WO	9910607	3/1999
WO	WO 99/13185	3/1999
WO	9922095	5/1999
WO	WO 99/31158	6/1999
WO	9943904	9/1999
WO	99064692	12/1999
WO	WO 00/08271	2/2000
WO	0014354	3/2000
WO	WO 00/21901	4/2000
WO	WO 00/55446	9/2000
WO	WO 00/63506	10/2000
WO	0065166	11/2000
WO	WO 01/16048	3/2001
WO	0125561	4/2001
WO	0125562	4/2001
WO	WO 01/26894	4/2001
WO	WO 01/36191	5/2001
WO	0149952	7/2001
WO	0159228	8/2001
WO	0166485	9/2001
WO	0168547	9/2001
WO	WO 01/65021	9/2001
WO	0173239	10/2001
WO	0227109	4/2002
WO	0231287	4/2002
WO	WO 02/28795	4/2002
WO	WO 02/28796	4/2002
WO	WO 02/32830	4/2002
WO	0238518	5/2002
WO	WO 02/055806	7/2002
WO	WO 02/081839	10/2002

WO	WO 02/081840	10/2002
WO	WO 02/081841	10/2002
WO	WO 02/081842	10/2002
WO	2002096824	12/2002
WO	03106365	12/2003
WO	2004031093	4/2004
WO	2004063113	7/2004
WO	2005003478	1/2005
WO	2005019550	3/2005
WO	2005035900	4/2005
WO	2005068741	7/2005
WO	2005078210	8/2005
WO	05083191	9/2005
WO	2006039762	4/2006
WO	0608642	8/2006

## OTHER PUBLICATIONS

International Search Report for PCT/US 02/10610 dated Aug. 5, 2002.

International Search Report for PCT/US 02/10608 dated Aug. 5, 2002.

International Search Report for PCT/US 02/10609 dated Aug. 7, 2002.

Notice of Opposition for Chilean patent application No. 653-2002.

Notice of Opposition for Chilean patent application No. 655-2002.

Notice of Opposition for Chilean patent application No. 656-2002.

Notice of Opposition for Chilean patent application No. 654-2002.

Copending U.S. Appl. No. 10/117,561, filed Apr. 3, 2002 and pending claims.

Copending U.S. Appl. No. 10/117,549, filed Apr. 3, 2002 and pending claims.

Letter from Sargent & Krahn dated Apr. 11, 2005 reporting First Substantive Report for Chilean Patent Application No. 656-2002, which claims priority to U.S. Appl. No. 60/281,195, filed Apr. 3, 2001.

James Hardie article, "External Wall Cladding", Oct. 1990.

James Hardie article, "Primeline Weatherboards", Oct. 1996.

Notification of First Office Action for Chinese Patent Application No. 02811237.7 dated Mar. 18, 2005. Chinese Patent Application No. 02811237.7 is the Chinese National Phase of PCT/US02/10609, filed Apr. 3, 2002, which claims priority to U.S. Appl. No. 60/218,195, filed Apr. 3, 2001. The present application also claims priority to U.S. Appl. No. 60/281,195.

Chilean patent application 170-97 (S. Ind. Pizarreño, Dec. 5, 1997).

Chilean patent application 2673-97 (S. Ind. Pizarreño, Jan. 30, 1997).

Letter from Sargent & Krahn dated Apr. 11, 2005 reporting First Substantive Report for Chilean Patent Application No. 656-2002 dated Mar. 4, 2002, which claims priority to U.S. Appl. No. 60/281,195, filed Apr. 3, 2001.

Letter from Sargent & Krahn dated Jan. 31, 2005 reporting First Substantive Report for Chilean Patent Application No. 655-2002 dated Mar. 4, 2002, which claims priority to U.S. Appl. No. 60/281,195, filed Apr. 3, 2001.

Letter from Sargent & Krahn dated Apr. 1, 2005 reporting First Substantive Report for Chilean Patent Application No. 653-2002 dated Mar. 4, 2002, which claims priority to U.S. Appl. No. 60/281,195, filed Apr. 3, 2001.

BGC Fibre Cement "Ceramic Tile Floor Underlay" Apr. 2002, 7 pgs.

J.E. Mark, Applied Polymer Science 21st Century, pp. 209-222 (Clara D. Craver and Charles E. Carraher, Jr. ed., Elsevier 2000).

Hawley's Condensed Chemical Dictionary, Fourteenth Edition, Revised by Richard J. Lewis, Sr., published by John Wiley & Sons, Inc. pp. 447, 624, 903-904.

Database WPI, Section Ch, Week 1977,23, Derwent Publications Ltd., London, GB, XP002159268.

Database WPI, Section Ch, Week 1977,23, Derwent Publications Ltd., London, GB, XP002159269.

PCA (Portland Cement Assoc) article: "Concrete Homes—Fiber Cement Siding" (3 pgs) dated Sep. 13, 2005.

Notification of First Office Action issued on Sep. 24, 2004 to a related Chinese application, Appln No. 00815911.4.

- Notification of First Office Action issued on Feb. 4, 2005 to a related Chinese application, Appln No. 02811074.9.
- Notification of First Office Action issued on Mar. 18, 2005 to a related Chinese application, Appln No. 02811168.0.
- International Search Report in PCT/US2004/019980 dated Jun. 21, 2004.
- Examination Report for European Patent Application No. 00980518.5.
- U.S. Patent Application No. 10/873,723, filed Jun. 21, 2004.
- Ambrose et al., "Metakaoline Blended Cements: An Efficient Way to Improve GRC Durability and Ductility". Int. Congress GRC/87, 6<sup>th</sup> Biennial Congress of the GRCA, Oct. 20-23, 1987.
- De Silva P.S. et al., "Hydration of Cements based on Metakaolin: Thermochemistry", Adv. In Cem. Res. vol. 3, No. 12, Oct. 1990, pp. 167-177.
- Ray et al. "Use of DTA to determine the effect of Mineralizers on the Cement-Quartz Hydrothermal Reactions", Thermochemica Acta 250 (1995), pp. 189-195.
- Zdenek Sauman et al., "Influence Explanation of Siliceous Materials Additive to Cement as well as of Pastes Hydration and Their Treatment Temperature on the Lime Quantity Liberated by Rehydration", II Cemento, vol. 3, 1978, pp. 343-350.
- Office Action mailed Jul. 13, 2007 in U.S. Appl. No. 10/117,401.
- Office Action mailed Dec. 12, 2006 in U.S. Appl. No. 10/117,401.
- Office Action mailed Mar. 27, 2006 in U.S. Appl. No. 10/117,401.
- Office Action mailed Oct. 5, 2005 in U.S. Appl. No. 10/117,401.
- Office Action mailed Mar. 14, 2005 in U.S. Appl. No. 10/117,401.
- Office Action mailed Aug. 25, 2004 in U.S. Appl. No. 10/117,401.
- Office Action mailed Nov. 3, 2003 in U.S. Appl. No. 10/117,401.
- Two EPO Examination Reports in copending Application No. 02-719-435.6.
- Decision to Grant a Patent and an Examination Report for copending Japanese Application No. 2002-579593.
- Examiner's First Report for copending Australian Patent Application No. 2002250516 dated Dec. 14, 2006.
- Examination Reports in copending Chilean Application No. 656-02 dated 2005 and 2006.
- Notice of Registration and two Office Actions in copending China Application No. 02811237.7.
- Decision to Grant for Patent and Preliminary Notice of Objection in copending Korean Application No. 10-2003-7013036.
- Letters Patent for copending New Zealand Patent No. 528779.
- Certificate of Grant of Patent in copending Singapore Patent Application No. 200305728-8.
- Kuder, et al. "Extruded Fiber-Reinforced Composites for Building Enclosures" NSF Housing Research Agenda Workshop: Proceedings and Recommendations, Orlando, FL; Feb. 12-14, 2004, pp. 222-231.
- CSR RendaLine—External Wall Cladding System—Brochure, Jan. 2002.
- EPS Plaster Cladding Systems Technical and Installation Manual, Rockcote Architectural Coatings (NZ) Limited, Mar. 2003.
- Stoanz Trade literature, Nov. 2003.
- Stoanz Trade literature, Jan. to May 2004.
- PBS Distributors Ltd trade literature relating to Vent-Clad cladding system, Aug. 2003.
- Plaster Systems, LTD., "Insulclad cavity based exterior plaster cladding system specification," Feb. 2004.
- Plaster Systems, LTD., "Insulclad cavity based exterior plaster cladding system specification," Oct. 2003.
- Department of Building and Housing, "Compliance Document for NZ Bldg Code Clause E2," 2005.
- New Zealand Department of Building and Housing, "Non-flush finished joints," Jul. 1, 2005, Acceptable Solution E2/AS1 (extract from the New Zealand Building Code) (1 pg).
- Written Opinion of the International Searching Authority for PCT/US2004/019980 dated Dec. 20, 2005.
- International Preliminary Examination Report for PCT/US00/27451 dated Dec. 7, 2001.
- International Search Report for PCT/US00/27451 dated Feb. 2, 2001.
- International Preliminary Examination Report for Application PCT/US00/31729 dated Feb. 21, 2002.
- International Search Report for PCT/US00/31729 dated Feb. 21, 2001.
- International Search Report for PCT/AU00/00320 dated May 31, 2000.
- International Preliminary Examination Report for Application PCT/US02/10760 dated Feb. 3, 2003.
- International Preliminary Examination Report for Application PCT/US02/10610 dated Feb. 7, 2003.
- International Preliminary Examination Report for Application PCT/US02/10608 dated Feb. 14, 2003.
- International Search Report for Application PCT/US02/10609 dated Aug. 1, 2002.
- International Preliminary Examination Report for Application PCT/US02/10609 dated Apr. 22, 2003.
- International Preliminary Examination Report for Application PCT/US04/19980 dated Jul. 27, 2005.
- International Preliminary Examination Report for Application PCT/US01/10908 dated Apr. 6, 2002.
- International Search Report for PCT/US01/01908 dated Mar. 19, 2001.
- International Search Report for PCT/AU97/00692 dated Dec. 3, 1997.
- Translation of Taiwanese Patent Office Decision of Appeal and Opposition (App.#85114421).
- Supplemental European Search Report (EP 97943673) dated Mar. 27, 2001.
- International Search Report for AU 2004903567, filed Jun. 29, 2004.
- International Search Report for PCT/IB2005/050709 dated May 23, 2005.
- International Preliminary Report for PCT/IB2005/050709 dated Dec. 22, 2005.
- Hardihome Lap Siding with the Embossed EZ Line Alignment Aid, Mar. 2000, 4 pp.
- Kuroki et al., "Cement-Bonded Board Industry and Market in Japan and New Technology Developments," 1995, Forest Products Society, pp. 105-112.
- Gypsum Association, Fire Resistance Design Manual, 14th Edition 1994, pp. 33-34.
- Copending U.S. Appl. No. 10/117,561, filed Apr. 3, 2002 and pending claims.
- Copending U.S. Appl. No. 10/117,549, filed Apr. 3, 2002 and pending claims.
- Copending U.S. Application No. 10/117,561, filed Apr. 3, 2002 and pending claims.
- Copending U.S. Application No. 10/117,549, filed Apr. 3, 2002 and pending claims.
- J.E. Mark, Applied Polymer Science 21st Century, pp. 209-222 (Clara D. Craver and Charles E. Carraher, Jr. ed., Elsevier 2000).
- Hawley's Condensed Chemical Dictionary, Fourteenth Edition, Revised by Richard J. Lewis, Sr., published by John Wiley & Sons, Inc. pp. 447, 624, 903-904.
- Database WPI, Section Ch, Week 197723, Derwent Publications Ltd., London, GB, XP002159268.
- Database WPI, Section Ch, Week 197723, Derwent Publications Ltd., London, GB, XP002159269.

\* cited by examiner






FIG. 1A




FIG. 1B




FIG. 2




FIG. 3




FIG. 4




FIG. 5




FIG. 6




FIG. 7




FIG. 8






FIG. 9A





FIG. 9B



*FIG. 10*




FIG. 11A




FIG. 11B




FIG. 12




FIG. 13




FIG. 14A





FIG. 14B



*FIG. 15*




FIG. 16






FIG. 17A








FIG. 17B



A



B



C

FIG. 18






FIG. 19






FIG. 21





FIG. 22



*FIG. 23*




FIG. 24






FIG. 25




FIG. 26




FIG. 27




FIG. 28







FIG. 30



*FIG. 31*




FIG. 32A




FIG. 32B






FIG. 33




FIG. 34




FIG. 35




FIG. 36




FIG. 37




FIG. 38




FIG. 39




FIG. 40






FIG. 41




FIG. 42A




FIG. 42B




FIG. 43A




FIG. 43B




FIG. 44A

FIG. 44B





FIG. 45A

FIG. 45B



*FIG. 46*




FIG. 47




FIG. 48






FIG. 49B

FIG. 49A




FIG. 50




FIG. 51




FIG. 52




FIG. 53




FIG. 54





FIG. 55



*FIG. 56*






FIG. 57




FIG. 58




FIG. 59




FIG. 60




FIG. 61




FIG. 62




FIG. 63




FIG. 64






FIG. 65




FIG. 66




FIG. 67





FIG. 68






FIG. 70

**REINFORCED FIBER CEMENT ARTICLE  
AND METHODS OF MAKING AND  
INSTALLING THE SAME**

PRIORITY INFORMATION

This application claims priority to U.S. Provisional Patent Application No. 60/281,195, filed Apr. 3, 2001, the entirety of which is incorporated by reference herein.

BACKGROUND OF THE INVENTION

1. Field of the Invention

This invention in one embodiment relates to a fiber cement article that is locally reinforced by a material to assist in the handleability, performance and durability of the article.

2. Description of the Related Art

The market for fiber cement siding for new home construction and home refurbishing markets in the United States is presently strong, due in large part to favorable economic conditions and the durability of fiber cement.

Siding materials have traditionally been either solid or thin resilient materials. Vinyl and aluminum are two common examples of thin resilient siding materials. Vinyl siding is a thin resilient material that is shaped into the desired profile in a plastic state after extrusion of a compounded hot melt. Vinyl siding is commonly about 0.040 to 0.080 inches thick. However, vinyl presents problems as a plank material because it has a high rate of thermal expansion, which is undesirable for a product exposed to a wide range of temperatures. Aluminum siding is another example of a thin shaped product and typically has a thickness of about 0.010 to 0.030 inches. The vinyl and aluminum profiles often have an installed shape similar to traditional solid wood siding, but often include an interlocking feature to assist with the ease of installation. The interlocking profiles are usually engaged in an upward motion against gravity.

It is aesthetically pleasing for siding materials in the form of horizontal planks or laps to have a strong "shadow line" or perceived thickness such that individual planks can be discerned from a distance. This is evident from the design trends of thin vinyl or aluminum siding panels, which can be molded or extruded to give the appearance of thick, individual wood planks.

There are a number of different solid siding materials that are used in the construction and refurbishing industry. Wood siding, hardboard and fiber cement siding are examples of commonly used solid siding materials. Wood tends to lack durability and is susceptible to burning and termite attack and is not sufficiently durable in moist environments, e.g., it rots upon prolonged exposure to water. The siding shapes of solid materials are usually formed by saw cutting, machining or routing from a starting rectangular shape. A thick shadow-line or thick bottom edge of a solid siding is usually attained by starting with a solid rectangular shape of at least the thickness of the finished bottom edge of the siding. The solid siding is then machined or cut into the desired structure.

While panels and planks made from wood, wood composites, and fiber-reinforced cementitious materials are inherently solid and thick, further increases in thickness of the fiber cement are not practical for reasons of material cost, weight and handling characteristics of long siding planks. Rather, an assembly that allows the use of less material while maintaining perceived thickness when installed would be beneficial. Thus, what is needed is a more efficient design of siding with a thick bottom edge to create the traditional deep shadow line with a more efficient use of material.

In addition, what is needed is a way to form a vertically-installed stackable siding plank that secures the bottom edge from lateral forces and has hidden nailing for improved aesthetics under the lap of the siding planks. In addition, what is needed is a stackable siding as described above with the exterior durability of fiber cement that is more easily machined than traditional medium density fiber cement. Furthermore, what is needed is a siding that installs with ease, maintains a constant gauge of plank rows along the length of the siding and between rows of siding and preferably resists penetration of wind driven rain through the plane of the siding.

The handleability of a siding plank is a combination of the weight, stiffness, and elasticity of the plank. Although a siding plank should be self-supporting when balanced flat upon a support point, thin fiber cement siding planks manufactured by traditional methods can be brittle and break during manual transport. While thin fiber cement siding planks could be transported by handling the edges of the planks, this slows the installation process. Therefore, what is needed is a way to improve the handleability of thin fiber cement planks.

Resistance to the effects of water and biological attack, low density, and good dimensional stability make fiber cement useful in residential and commercial building applications. However, the tensile strength of fiber cement is low relative to other building materials such as steel, aluminum, wood, and some engineered plastics. The range of application for fiber cement products could be greatly extended if fiber cement articles could be reinforced in key areas where additional tensile or impact strength is required for a specific application. What is needed is a way to provide localized reinforcement to fiber cement articles.

SUMMARY OF THE INVENTION

In one preferred embodiment of the present invention, a reinforced article is provided that is comprised of a piece of fiber cement having a front surface and a back surface and a reinforcing fixture bonded along a length of at least one of the front surface and the back surface. Attaching the reinforcing fixture to the piece of fiber cement improves the strength of the fiber cement article and improves the durability and handleability of thin pieces of fiber cement. The reinforcing fixture can include, but is not limited to, a metal foil, woven metal mesh, polymer film, polymer fabric mesh, or a mesh nailing skirt. The reinforcing fixture preferably has a higher tensile strength than that of the fiber cement, and in one embodiment, is made of a less rigid material than that of the fiber cement. Preferably the reinforcing fixture is bonded to the fiber cement piece by a high shear adhesive. In one embodiment, wherein the fiber cement article is provided with a foil backing bonded to it using a durable high-shear adhesive, the foil backing functions as a heat reflecting fixture. In another embodiment, a multiple lap fiber cement article is provided that includes at least one fiber cement plank bonded in an overlapping fashion to another fiber cement plank using a durable, high-shear adhesive layer.

A further brief description of other embodiments that may be used in conjunction with the foregoing embodiments is presented below.

In one aspect, a fiber cement (FC) siding plank having an interlocking feature is provided that allows siding planks to be stacked in a manner that creates a uniform and deep shadow line and secures the planks against lateral forces by blind nailing instead of face nailing. Preferably, the interlock-

ing feature also helps set the horizontal gauge of the exposed plank face and allows for leveling of the planks during installation.

In one embodiment, the interlocking feature of the FC siding plank comprises matching lock and key cutouts on opposite ends of the plank. Preferably, the lock and key use gravity to help mate two fiber cement siding planks tightly and uniformly so as to maintain consistent gauge and overlap and create a uniform shadow line without face nailing. The plank is secured from lateral forces by hidden nailing under the lap of the adjacent plank. Preferably, the FC siding plank is low-density and can be easily machined.

Furthermore, the siding plank may include a built-in fixing indicator that allows the installer to quickly determine the proper region to affix the nail. Preferably, the fixing indicator is formed on the FC siding plank using an extrusion process so that the fixing indicator is formed cost-effectively along with the FC siding plank. The fixing indicator ensures proper placement of the fixing device within a predetermined nailing region. The predetermined nailing region on the siding plank is preferably the overlap region with the adjacent plank so that the nail or other fastener can be hidden from view. Moreover, fixing voids or hollows can also be formed beneath the fixing indicator to relieve stress that can lead to break out and cracking of the product when nailed or fastened to wall framing.

In another embodiment, the interlocking feature of a FC siding plank comprises an oversized "V" style lock and a key tip. The lock can be separately attached to the FC plank or integrally formed as part of the plank. Preferably, the siding plank interlocks with an adjacent plank by locking the oversized "V" style lock into the key tip on an upper edge of the adjacent plank. The lock maintains a constant gauge and overlap between the planks so as to create a uniform and thick shadow line. The oversized "V" style lock design allows for non-uniform flatness of a framed wall and maintains a constant gauge of plank rows along the length of the siding and between rows of siding. The plank is secured from lateral forces by hidden nailing under the lap of the plank. Preferably, the lock also comprises compressible regions, which allows the planks to be easily interlocked during installation and provides lateral compensation for non-planar mounting surfaces. The compressible material can also act as a seal against wind and rain.

In another embodiment, the interlocking feature of a siding plank comprises a square lock system. Preferably, the square lock system comprises a square lock, a butt piece, and an overlap guide. It can be appreciated that the square lock system, as well as the other systems described herein, can be applied to a variety of siding planks, including but not limited to FC planks. Preferably, the square lock is configured to fit over an upper edge of an adjacent plank in a manner such that a small gap may be maintained between the lock and the upper edge of the adjacent plank to accommodate variable gauge height. The square lock helps level the planks during installation and allows for small variations in the siding installed gauge while reducing lateral movement of the planks. The square lock can be separately bonded to the siding plank or formed as an integral part of the FC siding plank. Preferably, the square lock has one or more dove tail grooves to enhance the bonding between the lock and the siding plank. The square lock design preferably resists penetration of wind driven rain through the plane of the siding.

Furthermore, the siding plank of one preferred embodiment may also include an apparatus for reducing capillary action between adjacent overlapping planks. Preferably, the apparatus comprises a capillary break formed by adding to or

indenting the material of the interlocking device of the siding plank assembly. Preferably, the capillary break is placed between adjacent siding planks to stop the rise of water in the plank overlap region and thus provide additional moisture protection to the exterior barrier wall and siding interior without leaving a gap that is attractive to insects.

In another aspect, a lightweight, two-piece FC siding plank is provided that produces a uniform and thick shadow line when stacked with other planks. The two-piece FC siding plank generally comprises a main plank section and a FC butt piece that is bonded to the main plank section and extends partially over a back surface of the main plank section. The butt end piece reinforces the main plank section to increase the overall rigidity of the plank. The thickness of the butt piece also helps to create a deeper shadow line on adjacent planks. Preferably, the butt piece is separately bonded to the main plank section so that the enhanced shadow line is created without having to machine a single rectangular FC material to form the equivalent structure.

The adhesive used to bond the two pieces together can be polymeric, cementitious, organic or inorganic or a combination thereof such as polymer modified cement. The adhesive may also have fiber added to increase the toughness of the adhesive joint. In one embodiment, the main plank section is bonded to the butt piece using a fast setting, reactive hot-melt polyurethane adhesive. Preferably, the polymeric adhesive establishes a very quick bond which enables a machining operation to follow the bonding operation in a single manufacturing line rather than having to wait for the adhesive to set and then machine in a separate operation.

In another embodiment, the main plank is adhered to the butt piece using a cementitious adhesive that is compatible with fiber cement materials and thus can be bonded to the FC main plank while in a green state and co-cured with the FC material to form a durable bond. Preferably, a pressure roller system or a hand roller is used to bond the main siding plank to the butt piece. A hydraulic press can be used to bond the two pieces if the siding plank or butt piece has uneven surface. Additionally, in other embodiments, the two-piece FC siding plank can also be formed by extrusion in which a single piece of FC plank with an integrally formed butt piece is formed. Furthermore, the main plank section and the butt piece can have hollow centers to further reduce the weight of the siding plank.

In another embodiment, a two-piece FC siding plank includes an interlocking feature that mates two FC siding planks tightly and uniformly without requiring a visible nail or other fastener to fasten the overlapping region of the two planks. Preferably, the interlocking feature comprises a key formed on the main plank and a lock formed on the butt piece. The key fits into the lock and, with the help of gravity, interlocks adjacently mounted planks. The lock and key set the gauge of the exposed plank face without requiring frequent measuring.

In another aspect, an adhesive composition is provided that is used to bond cementitious materials, such as fiber cement planks. Preferably, the adhesive composition includes cement, silica, a thickener, and water, and may include organic or inorganic fibers. The adhesive composition can be used to bond flat sheet, plank or profiled cementitious bound building products. The adhesive can also be used to bond different density cementitious materials together to form a composite panel. In one embodiment, the adhesive is used to bond two fiber cement siding planks together. Preferably, the adhesive is applied to the fiber cement planks in a green state so that the FC and FC adhesive cure together. Preferably, the

adhesive does not deteriorate under autoclave processing conditions and thus can be used to bond FC planks prior to autoclaving.

In another aspect, a siding plank having a spline is provided that increases the handling, strength and stiffness of the siding plank and produces a uniform and thick shadow line. The spline can be a shaped piece of one or more materials, and is preferably made of lightweight materials such as plastic, foamed plastic, metal or fiber reinforced plastic. The spline is preferably attached to the main body of the siding plank to add function and/or aesthetics to the plank. Preferably, the spline improves the handleability and toughness of the siding plank. With the spline, the thickness of a medium density FC plank can be reduced without sacrificing handleability. For instance, FC planks that are about  $\frac{1}{4}$  to  $\frac{3}{16}$  inch thick can still be handleable without breaking at 16 ft length when the spline is attached to the plank. This provides a lightweight FC siding plank of increased length that is easier to handle and requires less material to manufacture.

In one embodiment, the spline comprises a butt and a lock and is designed for use in combination with a FC plank. Preferably, the butt is thick so that a deep shadow line can be produced when the planks are stacked together. Preferably, the lock is an angled lock that is configured to help secure the plank to adjacent planks in the stack. Preferably, the spline is bonded to the to the FC plank with an adhesive and the spline has one or more dovetail grooves in the adhesive surface area to strengthen the bond between the spline and the plank. In another embodiment, the spline has an overlap guide that helps set the gauge of the exposed plank face. However, it can be appreciated that the spline does not have to include a lock, an overlap guide or dovetail grooves.

It will be appreciated that the preferred embodiments of this invention are not limited to siding planks or interlocking features to mount one plank adjacent another. Thus, in one embodiment a fiber cement article, which may or may not be a siding plank, is provided having a reinforcing fixture adhered thereto. The reinforcing fixture provides localized reinforcement to areas of the article that requires additional strength and/or support.

These and other objects and advantages will become more fully apparent from the following description taken in conjunction with the accompanying drawings.

#### BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1A shows an isometric view of one embodiment of a FC siding plank with a back surface visible.

FIG. 1B shows an isometric view of FC siding plank with a front surface visible.

FIG. 2 shows an end view of FC siding plank.

FIG. 3 shows a siding system of FC siding planks affixed to a mounting surface.

FIG. 4 shows a method of installing a siding system according to one embodiment of the present invention.

FIG. 5 shows an isometric view of a section of an FC plank in accordance with another embodiment of the present invention.

FIG. 6 shows an end view of an extrusion die used to form the plank of FIG. 5.

FIG. 7 shows a cross-sectional view of a siding plank system in accordance with the embodiment of FIG. 5 affixed to a mounting surface.

FIG. 8 shows an isometric view of a section of an FC plank in accordance with another embodiment of the present invention.

FIG. 9A shows an isometric vertical view of a two-piece FC plank in accordance with another embodiment of the present invention.

FIG. 9B shows an isometric horizontal view of the two-piece FC plank of FIG. 9A.

FIG. 10 shows a side view of a first end of a butt piece used to form the plank of FIG. 9A.

FIG. 11A shows an isometric view of the two-piece plank of FIG. 9A formed using a pressure roller system.

FIG. 11B shows an end view of the two-piece plank and pressure roller system of FIG. 11A.

FIG. 12 shows one method for making a two-piece plank.

FIG. 13 shows another method for making a two-piece plank.

FIG. 14A shows an isometric view of a two-piece plank formed using a hand roller.

FIG. 14B shows an end view of the two-piece plank and hand roller of FIG. 14A.

FIG. 15 shows a method of making a two-piece plank assembly using an adhesive.

FIG. 16 shows a method of making a cementitious adhesive for bonding FC materials.

FIGS. 17A and 17B show schematic views of a Hobart style low shear mixer containing adhesive formulation in accordance with the method of FIG. 16.

FIG. 18A, 18B, 18C shows a dewatering apparatus containing mesh screens and a metal plate in accordance with the method of FIG. 16.

FIG. 19 shows a high shear mixer containing an adhesive formulation in accordance with the method of FIG. 16.

FIG. 20A shows a partial perspective view of a two-piece FC plank assembly according to another embodiment of the present invention.

FIG. 20B shows a partial perspective view of a two-piece FC plank assembly rotated 90° from FIG. 20A.

FIG. 21 shows a side view of the plank assembly of FIG. 20A.

FIG. 22 shows a cross-sectional view of two installed plank assemblies of FIG. 20A.

FIG. 23 shows a method of the installing plank assemblies of FIG. 20A.

FIG. 24 shows an isometric view of another embodiment of the FC plank assembly.

FIG. 25 shows a cross-section of the plank assembly of FIG. 24.

FIG. 26 shows a key tip on the FC plank assembly of FIG. 24.

FIG. 27 shows an enlarged cross-sectional view of the lock assembly on the FC plank assembly of FIG. 24.

FIG. 28 shows a cross-sectional view of the lock assembly of FIG. 27 with approximate dimensions.

FIG. 29 shows a cross-sectional view of lock assembly and key of two adjacent FC plank assemblies.

FIG. 30 shows a cross-sectional view of a siding system made up of two-piece planks with oversized "V" style lock and compressible regions in accordance with FIG. 24.

FIG. 31 shows a method of making the plank of FIG. 24 with an oversized "V" style lock and compressible regions.

FIGS. 32A and 32B show alternate cross-sectional views of plank designs that could utilize first and second compressible regions.

FIG. 33 shows an isometric view of a section of a siding plank assembly with a locking spline in accordance with another embodiment of the present invention.

FIG. 34 shows an isometric view of the plank of FIG. 33.

FIG. 35 shows a cross-sectional view of the plank of FIG. 33.



FIG. 36 shows an isometric view of the locking spline of FIG. 33.

FIG. 37 shows a cross-section of the locking spline of FIG. 33.

FIG. 38 or end view shows an end view of the locking spline of FIG. 33, with approximate dimensions.

FIG. 39 shows a cross-sectional view of the siding plank assembly of FIG. 33.

FIG. 40 shows a cross-sectional view of an alternative siding plank assembly having a locking spline with a chamfer.

FIG. 41 shows a cross-sectional view of the two-piece siding plank system of FIG. 33 affixed to a mounting surface.

FIG. 42A shows a cross-sectional view of a plastic spline having a capillary break and dovetail grooves.

FIG. 42B shows an enlarged cross-sectional view of a surface of the spline of FIG. 42A having dovetail grooves.

FIG. 43A shows a cross-sectional view of the spline of FIG. 42A bonded to a main plank.

FIG. 43B shows an enlarged cross-sectional view of the bond between the spline and main plank of FIG. 43A.

FIG. 44A shows a cross-sectional view of a two-piece siding plank assembly in accordance with another embodiment of the present invention.

FIG. 44B shows a cross-sectional view of the two-piece siding system of FIG. 44A affixed to a mounting surface.

FIG. 45A shows a cross-sectional view of the two-piece siding plank assembly in accordance with another embodiment of the present invention.

FIG. 45B shows a cross-sectional view of the siding system of FIG. 45A affixed to a mounting surface.

FIG. 46 shows the method steps for making a two-piece plank assembly using an FC siding plank bonded with an adhesive to a plastic spline.

FIG. 47 shows an isometric view of a section of a siding plank assembly in accordance with another embodiment of the present invention.

FIG. 48 shows an isometric view of the plank of FIG. 47.

FIG. 49A shows a cross-sectional view of the plank of FIG. 48.

FIG. 49B shows a side view of the key tip of FIG. 49A.

FIG. 50 shows an isometric view of the locking spline of FIG. 47.

FIG. 51 shows a cross-sectional view of the locking spline of FIG. 50.

FIG. 52 shows an end view of the locking spline of FIG. 50 with approximate dimensions.

FIG. 53 shows a cross-section of the siding plank assembly of FIG. 47.

FIG. 54 shows a cross-sectional view of an alternative siding plank assembly with a chamfer.

FIG. 55 shows a cross-sectional view of the two-piece siding plank system of FIG. 47 affixed to a mounting surface.

FIG. 56 shows a method for making a two-piece plank assembly using an FC siding plank bonded with an adhesive to a plastic spline.

FIG. 57 shows an isometric view of a section of a siding plank assembly in accordance with another embodiment of the present invention.

FIG. 58 shows an isometric view of the plastic spline with a capillary break of FIG. 57.

FIG. 59 shows a cross-sectional view of the spline of FIG. 58.

FIG. 60 shows an end view of the spline of FIG. 58 with approximate dimensions.

FIG. 61 shows a cross-sectional view of a two-piece siding plank system showing adjacent siding plank assemblies formed in accordance with FIG. 57.

FIG. 62 shows an isometric view of an alternative embodiment of plastic spline with a capillary break.

FIG. 63 shows a cross-sectional view of the spline of FIG. 62.

FIG. 64 shows an end view of the spline of FIG. 62.

FIG. 65 shows a cross-sectional view of a two-piece siding plank system showing adjacent siding planks formed using the spline of FIG. 62.

FIG. 66 shows a cross-sectional view of a reinforced fiber cement article.

FIG. 67 shows a front perspective view of a reinforced fiber cement plank with a nailing skirt.

FIG. 68 shows a rear perspective view of a reinforced fiber cement plank with an extruded polymer reinforcing strip.

FIG. 69 shows a rear perspective view of a multi-lap fiber cement plank.

FIG. 70 shows a method of making a reinforced fiber cement article.

#### DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

Certain preferred embodiments of the invention generally relate to lightweight siding plank assemblies that are structured to secure the siding planks against lateral forces without face nailing and to create a uniform and deep shadow line. In some of these embodiments, the shape of the plank is achieved by adding a second material to a base plank to add function and/or aesthetics, such as a thick bottom edge and/or interlock. These and other features and functionality of the preferred embodiments are described in detail below.

Unlike other siding materials, fiber cement ("FC") materials have preferred qualities of non-combustibility, strength, and durability. Low-density FC has additional advantages over higher density FC because the material is more easily machined, and its decreased weight facilitates handling and installation. Manufacture of siding planks made of low-density and medium-density FC material, as described in Australian Patent No. AU 515151 and U.S. Pat. No. 6,346,146, the entirety of each of which is hereby incorporated by reference, having additional functional and aesthetic features could result in a more marketable siding plank.

One siding design, which uses a lock system, allows planks to be locked into one another without requiring extensive measurement to maintain gauge (the visible vertical distance between planks) and overlap (the vertical distance the plank overhangs the plank below) during installation. Although this lock design has many inherent advantages, this design affords little to no flexibility when being installed on a non-planar wall. Therefore, embodiments described below include a locking plank that allow the exterior siding to be installed on non-planar walls.

Moreover, certain lock designs do not function satisfactorily for small variations in gauge that are sometimes desired by installers, especially when trying to level-out inaccuracies in framing and installation around window and door openings. As a result of poorly fitted V-type lock and key siding, the plank may subsequently experience lateral movement (flapping) when subjected to wind. Rather, a lock design that allows for small variations in gauge while preventing lateral movement (flapping) when subjected to wind would be beneficial.

Furthermore, functional performance enhancements made to existing FC siding planks will bring great value to the siding plank market. For example, an alignment feature or fixing indicator, described below, adds value to FC siding planks by facilitating the installation process. Also, the

appearance of nailable extruded products on the market has brought with it the need to provide nailing positions on the product to ensure proper and speedy installation. Accordingly, there is a sound business motivation to find a cost efficient way to add features such as affixing indicators to FC siding planks. Moreover, what is needed is also a way to form a stackable siding plank that secures the bottom edge from lateral forces and allows for hidden nailing under the lap of the siding planks, as described below.

Although the preferred embodiments of the present invention describe the use of fiber cement planks, it will be appreciated that other materials may be used as well. It will also be appreciated that the invention is not limited only to siding planks, but may have use in other applications as well.

#### I. Low-Density Siding Plank with Locking Features and Method of Installing the Same

At least one embodiment relates to a low density plank with locking features and methods of installing the same. In one embodiment, the siding plank is manufactured using a process, which includes but is not limited to the Hatschek process as described in U.S. Pat. No. 6,346,146, the entirety of which is hereby incorporated by reference, to make low-density FC materials. Low density fiber cement typically has a density ranging from about 0.7 to 1.2 g/cm<sup>3</sup>, whereas medium density typically has a density of about 1.3 to 1.5 g/cm<sup>3</sup>. This embodiment includes locking features to allow siding planks to be interlocked when installed on a mounting surface (e.g., an exterior wall) as siding.

FIG. 1A and FIG. 1B show two isometric views of a siding plank 1100. As shown in FIG. 1A, siding plank 1100 includes a back surface 1110, an end surface 1115, a key 1130, and a lock 1140. As shown in FIG. 1B, siding plank 1100 further includes a front surface 1120. Table 1 shows preferred ranges of siding plank dimensions for this embodiment:

TABLE 1

Preferred range of siding plank dimensions	
Dimension	Range
Thickness T	about 3/16-1/2 inch
Width W	about 5-12 inches
Length L	about 12-16 feet

FIG. 2 shows an end view of siding plank 1100 that further describes key 1130 and lock 1140. Specifically, key 1130 further includes a key tip 1132 and makes an angle 1135 with a vertical plane. The key tip preferably forms a tier indented in the front surface of the plank. However, it will be appreciated that the key tip need not have a tier, and may have a variety of shapes and configurations, including those described below. Lock 1140 makes an angle 1145 ( $\theta$ ) with a vertical plane. Angle 1135 ( $\theta$ ) ranges in one embodiment from about 85 degrees to 30 degrees, and is preferably about 45 degrees. Angle 1145 preferably is approximately equal to angle 1135.

A commercially available spindle molder (not shown) is used in one embodiment to machine key 1130 and lock 1140 into siding plank 1100. A spindle molder is similar to wood-cutting equipment; however, it is equipped with polycrystalline diamond (PCD) blades for improved performance in cutting FC products. Conventional machining methods for shaping FC material are used to cut the siding plank. The use of low density fiber cement is especially advantageous because it enables easy machining of the material and greater tool life. End surface 1115 is rectangular prior to machining.

FIG. 3 shows a cross-sectional view of siding system 1500. As shown in FIG. 3, a first nail 1540 rigidly attaches a first siding plank 1510 to a mounting surface 1560, such that first nail 1540 is completely hidden by the overlap (called "blind nailing"). Mounting surface 1560 is typically a series of wall studs. Key 1130 of first siding plank 1510 is inserted into lock or overlap region 1140 of second siding plank 1520. A second nail 1550 rigidly attaches a second siding plank 1520 to mounting surface 1560. The gap 1530 created between first siding plank 1510 and second siding plank 1520 should be of a size that is aesthetically pleasing. First siding plank 1510 and second siding plank 1520 are substantially identical to siding plank 1100 shown in FIG. 1A, FIG. 1B, and FIG. 2.

FIG. 4 shows a method 1600 of installing siding planks onto a mounting surface to form a siding system, which involves:

**Mounting first siding plank 1610:** First siding plank 1510 is placed against mounting surface 1560 as shown in FIG. 3. First nail 1540 is driven into first siding plank 1510 near its upper edge to rigidly attach it to mounting surface 1560.

**Aligning lock and key features 1620:** Second siding plank 1520 is placed against mounting surface 1560 above first siding plank 1510 such that lock 1140 of second siding plank 1520 is aligned with key 1130 of first siding plank 1510, as shown in FIG. 3.

**Lowering second siding plank 1630:** Second siding plank 1520 is lowered onto first siding plank 1510. As second siding plank 1520 is lowered (with the help of gravity) onto first siding plank 1510, key 1130 of first siding plank 1510 automatically engages and aligns lock 1140 of second siding plank 1520 into a locked position. In this locked position, key 1130 of first siding plank 1510 prevents second siding plank 1520 from moving under the influence of wind forces, and therefore prevents wind-induced damage. Further, the locked position fixes the gauge and overlap, and creates a uniform shadow line, as shown in FIG. 3.

**Mounting second siding plank 1640:** Second nail 1550 is driven into second siding plank 1520 near its upper edge to rigidly attach it to mounting surface 1560. The method is then repeated to cover the mounting surface to form a larger siding system.

The embodiment described above has several advantages over the prior art. For instance, it avoids face nailing. Because nails are often used to achieve a tight and uniform fit between two siding planks, it is aesthetically preferable to avoid face nailing because the nail head cannot be hidden when finished. Advantageously, the siding plank assembly of this embodiment provides a way to mate two FC siding planks tightly and creates a uniform shadow line without requiring a face nail to fasten the two siding planks.

In addition, another advantage is that the embodiment uses gravity during installation to obtain a secure fit between the siding planks. Conventional siding planks such as vinyl offer interlocking features that require an upward motion against the force of gravity to interlock two adjacent siding planks into place. A more natural downward motion, taking advantage of the force of gravity, facilitates installation. Advantageously, the assembly of this embodiment uses gravity to help interlock the planks.

A further advantage of this embodiment is that it allows the nail or fastener to penetrate directly through the fiber cement plank, in contrast to conventional fiber cement siding planks that are adhered indirectly to a mounting surface. Direct fastening of the fiber cement plank can occur with the fastener penetrating through the plank to attach the plank to the mounting surface.

Moreover, siding planks in the prior art are often subjected to wind forces that may separate the siding planks from their mounting surface. The embodiment described above reduces the likelihood of damage caused by wind forces.

The “shadow line” is created by the thickness of a siding plank’s bottom edge, which casts a shadow on the siding plank directly below it. A uniform shadow line is aesthetically desirable, and is usually achieved by face nailing the siding planks. The embodiment described above produces a uniform shadow line between two siding planks without requiring a face nail to fasten the siding planks.

Installers of exterior siding planks balance the desire to install the siding planks quickly against the need to carefully measure the gauge and overlap for consistency. Gauge is the visible vertical distance between siding planks, and the overlap is the vertical distance that an upper siding plank overhangs a lower siding plank. The key and lock features described above make installation of the siding planks progress more quickly, because the design of the siding planks maintain a consistent gauge and overlap without the need for these properties to be measured.

It will be appreciated that the lock and key of the siding plank assembly described above is not limited to planks formed of a single piece of material. Thus, as described in further embodiments below, multiple piece siding systems may be used to form the desired aesthetic and functional aspects of the assembly.

## II. Siding Planks Having an Extruded Fixing Indicator

In another embodiment, a plank is provided that has a fixing indicator and a fixing void or hollow beneath the fixing indicator. Described herein is a fiber cement product having a fixing indicator and a fixing void or hollow beneath the fixing indicator, and an apparatus for extruding an FC product having a fixing indicator. The result is an FC product that is easy to install and insures proper placement of the fixing device within a predetermined nailing region.

FIG. 5 shows an isometric view of the FC plank of a preferred embodiment. Plank **10100** includes a plank front or outer surface **10110**, a fixing indicator **10120** located in proximity to a plank first or upper edge **10130**, a plank back or inner surface **10140**, and an overlap region or locking region **10150** located in proximity to a plank second or lower edge **10160**. Plank **10100** is preferably a siding plank manufactured of FC using a conventional extrusion process. Fixing indicator **10120** is a depression in plank outer surface **10110** formed by an extrusion die as shown in FIG. 6. Likewise, overlap region **10150** is a depression in plank inner surface **10140** formed by the extrusion die shown in FIG. 6.

FIG. 6 is an end view of extrusion die **10200** of a preferred embodiment. Extrusion die **10200** includes a die outlet **10210** having a die outlet upper surface **10220**, a fixing indicator dimple **10230**, located in proximity to a die outlet first edge **10240**, a die outlet lower surface **10250**, and an overlap region form **10260** located in proximity to a die outlet second edge **10270**. Extrusion die **10200** is a conventional extrusion die for use with FC mixtures. The opening of die outlet **10210** is shaped to form plank **10100** of FIG. 5 as follows:

die outlet upper surface **10220** forms plank outer surface **10110**;

fixing indicator dimple **10230** forms fixing indicator **10120**;

die outlet first edge **10240** forms plank first edge **10130**;

die outlet lower surface **10250** forms plank inner surface **10140**;

overlap region form **10260** forms overlap region **10150**;

and

die outlet second edge **10270** forms plank second edge **10160**.

Fixing indicator dimple **10230** has a depth “d,” a width “w,” and is a distance “a” from die outlet first edge **10240**. Preferably, the fixing indicator will comprise an embossed feature between 0.015 and 0.080 inches deep and more preferably between 0.035 and 0.055 inches deep. The indicator can be in the form of a regular or irregular geometric form or a symbol or letter that covers an area of approximately 0.0015 square inches to approximately 0.25 square inches, more preferably between 0.015 square inches and 0.0625 square inches.

FIG. 7 shows a siding plank system of a preferred embodiment. Siding system **10300** includes planks **10100A** and **10100B**, a wall **10310**, and a nail **10320**. Using a conventional blind nailing technique, plank assemblies **10100A** and **10100B** are fixedly connected to wall **10310** using nails (or screws, or staples). FIG. 7 shows nail **10320** positioned in fixing indicator **10120** of plank **10100A** and driven through plank **10100A** into wall **10310**. When installed, plank **10100B** is positioned such that overlap region **10150** of plank **10100B** covers nail **10320** and fixing indicator **10120** of plank **10100A**. The first or upper edge **10130** of the plank thus forms a key tip that encases the overlap or locking region **10150**.

It can be seen in FIG. 7 that fixing indicator **10120** of a preferred embodiment insures that nail **10320** is not too close to the edge of plank **10100A**, thereby preventing cracking or splitting of plank **10100A**. Additionally, it can be seen that fixing indicator **10120** insures that nail **10320** is well within overlap region **10150** and is therefore not visible when installed.

Another embodiment, not shown, is an FC product having a plurality of fixing indicators **10120** in various locations on the outer surface of plank **10100**.

Another embodiment, not shown, is an FC product having a groove on the inner surface of plank **10100** formed by extrusion similar to fixing indicator **10120** and used for gluing plank **10100** to wall **10310** of FIG. 7.

In yet another embodiment, the fixing indicator could be formed using a post-extrusion marking technique, such as using a manual embossing in combination with a conventional Hatschek manufacturing process. Likewise, a manual embossing roller could be used in combination with a conventional extrusion process positioned in proximity to die outlet **10210** of extrusion die **10200** of a preferred embodiment.

As seen in FIG. 8, another embodiment has fixing void **10421** optionally included below the line of the fixing indicator to relieve stress that can lead to break out and cracking of the top edge of the product when nailed or fastened to wall framing or sheathing. The fixing void could be formed using mandrel in the extrusion formation process.

FIG. 8 shows an isometric view of the FC plank of a preferred embodiment. Plank **10400** is another example of an FC plank having a fixing indicator **10420**. Plank **10400** shows an example of an aesthetically pleasing pattern on the outer surface of plank **10400** formed by extrusion in similar fashion as fixing indicator **10420** and a fixing void or hollow **10421** below the line of the fixing indicator.

Advantageously, the siding plank assembly of this embodiment provides an inexpensive affixing indicator on siding planks which reduces damage to the planks at installation due to improper affixing. Furthermore, the installation time of an extruded FC product is also reduced. Additionally, the siding plank assembly provides an aesthetic appearance as it conceals the affixing by limiting the affixing region to the overlap area between adjacently stacked planks.

It will be appreciated that the fixing indicator could be formed using post-extrusion marking techniques such as, manual embossing, machining, ink jet or other printing, stamping, pressing, and painting techniques, which are all time-consuming and costly.

It will further be appreciated that the fixing indicator can be employed in several, if not all, of the siding plank assemblies described herein. For example, like the embodiment of FIGS. 1-3, the plank of FIG. 5 similarly contains a lock in overlap region 10150 and a key tip for insertion into the lock at first edge 10130. Thus, it can be seen that a fixing indicator can be placed similarly on the key 130 of FIG. 2.

### III. Two-Piece FC Plank and Method of Making the Same

In further embodiments, a two-piece FC plank and a method of making the same are provided. These two-piece planks can be used to form the various shapes described throughout this specification in order to provide a lock and key, hidden nailing, a deep shadow line, and other features described herein. Two methods for forming a two-piece FC plank are described below.

It will be appreciated that several manufacturing processes for bonding two pieces of FC material together to form a product use standard industry adhesives. However, due to the composition of the FC material and adhesive, the time it takes for the two pieces of FC material to adhere ("adhesion time") is lengthy and the bonding strength of the two FC pieces is weakened. Thus, bonding processes that use standard industry adhesives decrease the durability of installed siding panels and delay the post-processing of the product, which increase the manufacturing cycle time of the product. Advantageously, the bonding process of the below-described embodiments provide a quick process for bonding two FC pieces together to form a durable bond.

#### A. First Roller Method

FIGS. 9A and 9B show isometric views of a two-piece FC plank 2100. Two-piece plank 2100 includes a main plank section 2140, a second piece or butt piece 2130, a first end 2120, and adhesive 2110. Main plank section 2140 is preferably a medium-density FC and is typically about ¼ inch thick, but may be as thin as about ⅜ inch or less or as thick as about ½ inch or more. The width preferably ranges from about 5 to 12 inches, depending on the application. The length preferably ranges between about 12 to 16 feet, depending on the application. Main plank section 2140 may be manufactured with a smooth or textured surface. Further information regarding manufacture of main plank section 2140 may be found in Australian Patent No. AU 515151. Main plank section 2140 has an upper surface 2140U, also considered to be the back surface.

Butt piece 2130 is preferably made from a medium-density FC material, and is typically about ⅜ inch thick, but may be as thin as about ¼ inch or less, or as thick as about ⅝ inch or more. The width of butt piece 2130 is typically about 1½ inch, but may be as wide as about 2 inches or more, or as narrow as about ⅝ inch or less, depending on the application. The length is typically the same as main plank section 2140 (about 12 to 16 feet), depending on the application. Butt piece 230 has a lower surface 2130L, also considered the front surface. The function of butt piece 2130 is to reinforce main plank section 2140, thereby increasing the overall rigidity of plank 2100. A second function of butt piece 2130 is to provide thickness for an improved shadow line, a desired aesthetic quality.

Adhesive 2110, located between upper surface 2140U of main plank section 2140 and lower surface 2130L of butt piece 2130, in one embodiment is a fast setting, reactive

hot-melt polyurethane with a viscosity of about 10,000 to 100,000 CPS at application temperatures. Other embodiments for the adhesive 2110 are described below. The application temperature for adhesive 2110 ranges from about 200° to 325° F. The adhesion time ranges from about 3 to 5 seconds. The adhesion time is the time taken for the bond strength to develop after the adhesive is applied and nip pressing is performed.

In operation, adhesive 2110 is applied in beads on upper surface 2140U of main plank section 2140 along its length. This may be accomplished by using a Nordson hot-melt extrusion system. The adhesive beads are preferably spaced apart by a small distance, such as about 1" or ½". The preferred amount of adhesive is about 1 gram/foot/bead, though the amount may be as small as about 0.5 grams/foot/bead or as large as about 2 grams/foot/bead. Immediately upon applying adhesive 2110 (e.g., within about 3 seconds), lower surface 2130L of butt piece 2130 is interfaced with upper surface 2140U of main plank section 2140 such that first end 2120 of butt piece 2130 faces the center of main plank section 2140 as shown in FIG. 9A. The arrangement of main plank section 2140 and butt piece 2130 forms two-piece plank 2100 having an upper surface 2100U and a lower surface 2100L. Preferably the bottom surfaces of the main plank section 2140 and the butt piece 2130 are preferably flush.

As shown in FIG. 10, first end 2120 of butt piece 2130 makes an angle theta  $\theta$  of about 15 degrees, but may range from about 0 degrees to 60 degrees, with the horizontal plane. The function of the angled surface is to aid water drainage.

FIGS. 11A and 11B show isometric and end views, respectively, of a pressure roller system 2200 for squeezing main plank section 2140 to butt end 2130. System 2200 includes a first roller 2210, and a second roller 2220.

First roller 2210 and second roller 2220 are preferably opposing 7-inch diameter steel rollers and are arranged parallel to and adjacent one another with a gap in between. In operation, plank 2100 is fed through the gap between first roller 2210 and second roller 2220. The gap between roller 2210 and 2220 is sized to engage plank 2100 with an interference fit. Thus, first roller 2210 is in direct contact with upper surface 2100U of butt piece 2130, and second roller 2220 is in direct contact with lower surface 2100L of plank 2140. Plank 2100 is transported through roller system 2200 at approximately 50 feet/minute. As plank 2100 transverses through roller system 2200, first roller 2210 and second roller 2220 compress plank 2100 at a pressure of approximately 750 lb/inch of roller width for approximately 3 to 5 seconds.

FIG. 12 describes a method 2400 for making a two-piece medium density plank 2100, which involves:

**Melting adhesive 2410:** Fast-setting, reactive hot-melt polyurethane is melted in a hot-melt application system. One such system is commercially available from Nordson Corporation. Application temperatures range from about 200° to 325° F.

**Are the plank and butt piece flat? 2420:** The plank 2140 and butt piece 2130 are viewed for flatness. If plank 2140 and butt piece 2130 are determined to be flat, the process is continued to step 2430. If plank 2140 and butt piece 2130 are determined to be wavy or uneven, refer to method 2500, as shown in FIG. 13.

**Applying adhesive 2430:** Typically about 1 gram/foot/bead, but may be as small as about 0.5 g or as large as about 2 g, of hot-melt adhesive is applied in beads spaced about ½" to 1" apart on upper surface 2140U of main plank section 2140 (see FIG. 9A) using the Nordson Corporation system extrusion nozzle.

Placing butt-piece on adhesive **2440**: Buff-piece **2130** is placed onto adhesive **2110**, shown in FIG. 9A and as described above.

Maintaining pieces under pressure **2450**: Immediately (preferably within 3 seconds) upon completion of step **2440**, plank **2100** is passed through roller system **2200**, which maintains the plank under pressure (about 750 lb/inch of roller width) preferably for a minimum of 3 seconds to allow adhesive **2110** time to cool and bond with main plank section **2140** and butt piece **2130**. The squeezing of main plank section **2140** and butt end **2130** causes the beads of adhesive **2110** to spread out in a thin layer.

The method, shown in FIG. 12, is a process for maintaining pressure on plank **2100** when plank **2140** and butt piece **2130** are both flat. However, a further process was developed to bond surfaces that have variable flatness, shown in FIG. 13.

FIG. 13 describes another method **2500** for a making two-piece medium density plank **2100**, which involve:

Melting adhesive **2510**: Fast-setting, reactive hot-melt polyurethane is melted in a hot-melt application system. One such system is commercially available from Nordson Corporation. Application temperature of typically about 250°, but may range from about 200° to 325° F.

Are the plank and butt piece flat? **2520**: The plank **2140** and butt piece **2130** are viewed for flatness. If plank **2140** and butt piece **2130** are determined to be flat, refer to method **2400**, shown in FIG. 12. If plank **2140** and butt piece **2130** are determined to be wavy or uneven, continue process to step **2530**.

Applying adhesive **2530**: Typically about 1 gram/foot/bead, but may be as small as about 0.5 g or as large as about 2 g, of hot-melt adhesive is applied in beads spaced about 1/2" to 1" apart (a minimum of 2 beads are preferably applied) on upper surface **2140U** of main plank section **2140** (see FIG. 9A) using the Nordson Corporation system extrusion nozzle.

Placing butt-piece on adhesive **2540**: Butt-piece **2130** is placed onto adhesive **2110**, shown in FIG. 9A and as described above.

Maintaining pieces under pressure **2550**: Immediately (preferably within about 9 to 12 seconds) upon completion of step **2540**, plank **2100** is placed in a conventional hydraulic plate press or continuous press (not shown), which maintains the plank **2100** under pressure (about 750 psi) for a minimum of about 4 seconds to allow adhesive **2110** time to cool and bond with main plank section **2140** and butt piece **2130**. The squeezing of main plank section **2140** and butt end **2130** causes the beads of adhesive **2110** to spread out in a thin layer.

Advantageously, the two-pieces of FC material can be bonded quickly so that post-bonding processes can be initiated immediately. Furthermore, bonding two FC material members together is more cost-effective than machining a single rectangular FC section to form the equivalent structure. The siding plank assembly creates an enhanced shadow line by virtue of the first end of the butt end extending partially over the upper surface of the main plank section and provides a traditional cedar look with a thick butt edge. The butt end piece also results in increased rigidity of the FC panel product so that it can be easily handled and installed.

It will be appreciated that although the shapes described herein are formed from two pieces of fiber cement, an equivalent shape can be formed by machining a solid rectangular section. However, this method may be more costly and produce a high amount of waste material. It will also be appreciated that additional shapes can be produced, such as described below, by abutting the two pieces together.

B. Second Roller Method

In another embodiment, a cementitious adhesive mixture, described below, is located between upper surface **2140U** of plank **2140** and lower surface **2130L** of butt piece **2130**, as shown in FIGS. 9A and 9B. In operation, adhesive is applied to either upper surface **2140U** of plank **2140** or lower surface **2130L** of butt piece **2130** along its length. The thickness of applied adhesive **2110** is dependant upon the uniformity of textured surfaces **2130L** and **2140U**, typically in an amount that covers surfaces **2130L** or **2140U**, but preferably does not exceed about 1/8 inch.

As an alternative to the roller system described above, FIGS. 14A and 14B show plank assembly **3100**, and include a hand roller **3210** and an interleaver **3150**. Interleaver **3150** is a cured FC material used to support plank assembly and is in physical contact with lower surface **3140L** of the plank. In operation, hand roller **3210** is in functional contact with upper surface **3130U** of butt piece **3130**. Hand roller **3210** is rolled along the length of plank assembly and is used to apply pressure to upper surface **3130U** of butt piece **3130** while adhesive **3110** bonds plank **3140** and butt piece **3130** together.

FIG. 15 illustrates the process for making a two-piece medium density plank assembly with the cementitious adhesive, described below. The method involves:

Applying adhesive **3310**: Adhesive **3110** is applied to upper surface **3140U** of plank **3140**, shown in FIG. 14A, 14B.

Interfacing butt piece with plank **3320**: Lower surface **3130L** of butt-piece **3130** is interfaced with upper surface **3140U** of plank **3140**, shown in FIGS. 14A and 14B

Applying pressure to butt piece **3330**: Hand roller **3210** is rolled over the length of surface **3130U** of plank assembly **3100** in a direction normal to the upper **3130U** and lower **3140L** surfaces, shown in FIGS. 14A and 14B, to force contact of adhesive with fiber cement pieces, and provide adhesion between butt piece **3130** and plank **3140**.

Pre-curing adhesive **3340**: Plank assembly is air dried typically for about 12 hours, but may be as long as about 24 hours or more, or as short as about 8 hours or less.

Autoclaving plank assembly **3350**: Plank assembly is autoclaved at a temperature between about 350° to 400° F. at about 120 to 145 psi for a period of approximately 8 hours.

Trimming plank assembly **3360**: Overflow of cementitious adhesive **3110** is trimmed from cured and autoclaved plank assembly.

The use of a cementitious adhesive as described below to adhere the two pieces of fiber cement together has all of the advantages described above for the polymeric adhesive. Another advantage is that a cementitious adhesive is compatible with fiber cement materials, is economical and can be co-cured with the fiber cement pieces to form a durable bond.

#### C. Cementitious Adhesive Composition

The embodiments described above for adhering two pieces of fiber cement plank together in one preferred embodiment utilize a novel cementitious adhesive composition. Thus, one aspect of the present invention provides a composition of matter for, and method of making a cementitious adhesive for bonding materials, preferably FC materials, and more preferably medium density FC materials. The adhesive ingredients preferably include cement, silica, thickener, and water, and may include organic fibers or inorganic fibers. The adhesive formulation can be used to bond FC materials prior to autoclaving.

It will be appreciated that a preferred adhesive is able to withstand autoclave temperatures and is compatible with FC materials. Most conventional polymeric adhesives and polymer-modified adhesives melt, burn, or degrade when exposed to temperatures in excess of approximately 375 degrees F. During the manufacturing process, FC materials are dried in

an autoclave that can reach approximately 400 degrees F. Therefore, conventional polymeric adhesives cannot be used to bond FC materials prior to autoclaving.

Moreover, a preferred adhesive selected for use on FC materials should be compatible and as similar in composition as possible to the materials being bonded. This ensures that the system as a whole will respond to environmental factors in a similar manner within each component (environmental factors include temperature fluctuations, acid rain impacts, humidity, and wet-dry cycles). The adhesive and the FC materials will age similarly and thus will not weaken the system.

Advantageously, the adhesive composition of this embodiment can withstand curing temperatures in an autoclave and is compatible with the FC material to be bonded. Furthermore, the adhesive composition is less costly, more readily available, and more environmentally friendly compared with polymeric or polymer-modified adhesives. Unlike other adhesives, the adhesive composition also does not degrade under alkaline or moist conditions.

The cement, silica, and thickener are all added to the adhesive mix in powdered form, where the particle size for each ingredient may measure up to about 200 microns. The cement may be present in the formulation in an amount between about 10 and 90 wt %, the silica may be present in the formulation in an amount up to about 90 wt %, and the thickener may be present in the formulation in an amount up to about 2 wt %. Water may be present in the formulation in an amount up to about 90 wt %. (All references to weight in this document are provided on a dry material weight basis, unless otherwise indicated.)

The organic fiber in the formulation may be in the form of cellulose fiber (where the fiber may be bleached pulp), and may be present in the formulation in an amount up to about 5 wt %. The inorganic fiber in the formulation may be in the form of Wollastonite, and may be present in the formulation in an amount up to about 30 wt %. Both forms of fiber (organic and inorganic) may measure up to about 3 mm in length.

TABLE 2

Exemplifying formulations of cementitious adhesive.			
Raw Materials	Percent Raw Material by Dry Weight		
	Formulation 1	Formulation 2	Formulation 3
Organic fiber (e.g. bleached pulp)	0.5%	0%	0%
Cement	59.5%	59.7%	47.7%
Silica	39.5%	39.8%	31.8%
Inorganic fiber (e.g. Wollastonite)	0%	0%	20%
Thickener	0.5%	0.5%	0.5%
Water	430 to 470 milliliters of water per Kg of dry solids		

Table 2 shows three exemplifying formulations of cementitious adhesive. Each formulation contains cement to form the body of the bond, and fine-ground silica to react and bind with cement when autoclaved. The silica also acts as a filler/aggregate that lowers the cost of the matrix, without significantly reducing performance. Thickener slows the water being drawn from the slurry (adhesive) into the fiber cement. The presence of thickener ensures that the cementitious adhesive remains “tacky” during the bonding process of the fiber cement surfaces, ensures that the adhesive fills the gap between the pieces to be bonded, and “wets out” the second surface, which is necessary to develop a good cementitious

bond. The thickener also slows/reduces settling in the slurry and prolongs “open time” to add viscosity to the wet adhesive.

Formulation 1 and Formulation 3 additionally contain fiber to increase the bond strength. Both organic and inorganic fibers perform similarly in the formulation; however, organic fiber requires preparation for use, and inorganic fiber tends to be more costly to purchase than organic fiber. Although fiber adds strength to the adhesive formulation, it can also clog some applicators during use. To address this issue, Formulation 2 contains no fiber. Water is added as a necessary reactant for the cement in forming the hydrated cementitious bond. Water also provides the mixture “viscosity” necessary to mix the adhesive, to disperse fibers and solids through the mixture, and to apply the adhesive.

FIG. 16 shows a method 4100 of making cementitious adhesive for bonding medium-density FC materials that includes:

Step 4110: Does adhesive formula contain fiber? In this step, method 4100 proceeds to step 4112 if the formulation being made contains fibers. Otherwise, method 4100 proceeds to step 4115.

Step 4112: Does adhesive formula contain organic fiber? In this step, method 4100 proceeds to step 4130 if the formulation being made contains organic fibers. Otherwise, the formulation is presumed to contain inorganic fibers and method 4100 proceeds to step 4120.

Step 4115: Mixing silica, cement and water. In this step, method 4100 adds the powdered silica to water to produce a 50 wt % silica slurry, and then transfers the silica slurry to a mixer (such as a Hobart mixer). Method 4100 adds powdered cement and water to bring the percent by weight of solids to approximately about 68% to 70% (approximately about 430 to 470 milliliters total water per kilogram of solids), and then mixes the adhesive formulation for about five minutes to attain homogeneity in the mixture. An example of a Hobart mixer is shown in FIG. 17. Method 4100 then proceeds to step 4140. FIG. 17 is a schematic of Hobart style low shear mixer 4200 containing an adhesive formulation. Both views A and B include a Hobart mixing bowl 4210 and an adhesive formulation 4240. In view A, a ribbon blade 4220 blends adhesive formulation 4240, and in alternate view B, a whisk blade 4230 blends adhesive formulation 4240. Either blade may be used to obtain similar results.

Step 4120: Mixing silica, inorganic fiber, cement, and water. In this step, method 4100 adds the powdered silica to water to produce a 50 wt % silica slurry, and then transfers the silica slurry to a mixer (such as a Hobart mixer, shown in FIG. 17). Method 4100 adds the powdered cement and water, adds extra water to bring the percent by weight of solids to approximately 67% to 68% (approximately 470 to 500 milliliters total water per kilogram of solids), and mixes the adhesive formulation for about five minutes. Method 4100 then proceeds to step 4140.

Step 4130: Dispersing organic fiber in water. In this step, method 4100 adds the organic fiber, such as unbleached or bleached pulp. The pulp is previously hydropulped, refined, and diluted with water to about 0.4% by weight. Method 4100 mixes and disperses the organic fiber for approximately five minutes.

Step 4132: Mixing silica and cement. In this step, method 4100 adds the silica and then the cement to the organic fiber, and mixes the mixture. The preferable approach is to mix the ingredients of silica, cement, and fiber, then to blend the ingredients for five minutes in a mixer (such as a Hobart mixer, shown in FIG. 17) to attain homogeneity in the mixture.

Step **4134**: Dewatering mix (optional). Following step **4132**, a dewatering apparatus **4300**, shown in FIG. **18**, dewater the mix to achieve a thin paint consistency as described below. Method **4100** then proceeds to step **4140**.

FIG. **18** is a schematic of a dewatering apparatus **4300**, which includes a first side **4310**, a second side **4320**, a third side **4330**, and a fourth side **4340**. In one embodiment, each side of dewatering apparatus **4300** preferably has identical length, width, and height. In another embodiment, each side would measure approximately ten inches long and three inches high. The sides are arranged such that first side **4310** and third side **4330** are parallel to each other, second side **4320** and fourth side **4340** are parallel to each other, and each side is joined to two other sides at 90 degree angles (e.g., first side **4310** is arranged at a 90 degree angle to second side **4320** and fourth side **4340**), as shown in FIG. **18**.

Dewatering apparatus **4300** is designed to hold a perforated metal plate **4316**, a coarse mesh screen **4314** and a fine mesh screen **4312**. Views A, B, and C in FIG. **18** show plan views of screens **4312** and **4314**, and plate **4316**, respectively. Fine mesh screen **4312** conforms to ASTM#325; coarse mesh screen **4314** conforms to ASTM#10; and plate **4316** is approximately  $\frac{3}{16}$ " thick, and is perforated with round  $\frac{1}{4}$ " diameter holes **4317**, at a frequency of 9 holes per square inch. Screens **4312** and **4314**, and plate **4316** may be made of metal or other comparable materials to provide similar functionality.

In operation, the adhesive formulation is poured into dewatering apparatus **4300**. A set of mesh screens and a metal plate (not shown) identical to **4312**, **4314**, and **4316** are stacked in reverse order on top of the set inside **4300** so that the screens and plates are parallel to each other, and the adhesive formulation is contained between the two sets. Downward pressure applied to the screens and plates dewater the adhesive formulation. Water either exits through the bottom of dewatering apparatus **4300** or a vacuum apparatus (not shown) may optionally be used to remove pooled liquid from the top of the screens and plates.

Step **4140**: Transferring to high shear mixer. In this step, the adhesive formulation **4240** is added to a high shear mixer, as shown in FIG. **19**. FIG. **19** shows a high shear mixer **4400** containing an adhesive formulation **4240**. The adhesive formulation **4240** is added to a high shear mixing bowl **4410**, where a high shear mixing blade **4420** revolves at a speed sufficient to create a vortex in the center of the mixing bowl (approximately 6000 RPM) and completely integrate all ingredients.

Step **4142**: adding thickener. In this step, method **4100** adds thickener to high shear mixer **4400** as required to achieve a thick paint consistency. Thickeners may be made of commercially available cellulose derivatives, polyurethane and polyacrylate, such as "Bermocell" (cellulose ether), "Ethocel" (ethyl cellulose polymer), "Cellosize" (hydroxy ethyl cellulose), or "Natrosol" (hydroxyl ethyl cellulose and derivatives). One preferred thickener is "Natrosol Plus D430", a cellulosic derivative (hydrophobically modified hydroxy ethyl cellulose). The amount of thickener in one embodiment is nominally 0.5 wt %; however, more may be added to achieve the desired viscosity. A visual determination is sufficient to ascertain desired viscosity of the adhesive formulation.

It will be appreciated that other adhesives may be used to bond the FC materials. These include polymers or polymer-modified adhesives (called "thin-sets") to bond the FC materials. However, these products may not be suited for exposure to high temperatures in an autoclave. Plastics degrade at approximately 375 degrees F. and break down during auto-

claving. In addition, the polymers and polymer-modified adhesives are more costly to use compared with the preferred adhesives described above.

#### IV. Various Designs of Two-Piece FC Planks

The one and two-piece FC planks described above advantageously enable the formation of a variety of different shapes that provide a variety of desired features to the plank. Various designs are described below with respect to two-piece planks. However, it will be appreciated that similar shapes can be formed using one piece of material or other combinations of materials, such as described below.

##### A. Two-Piece Medium Density Plank with Locking Feature and Method of Making the Same

In one embodiment, a two-piece FC plank includes a butt piece having a lock such as described above. As shown in FIG. **20A** and FIG. **20B**, plank assembly **5100** includes a plank **5140**, a butt piece **5130**, and adhesive **5110**. In this embodiment, plank **5140** further includes a key **5160**, and butt piece **5130** further includes a lock **5150**.

FIG. **21** shows a side view of plank assembly **5100**. As shown in FIG. **21**, lock **5150** makes a lock angle **5285** with respect to horizontal line **5290**. Lock angle **5285** in one embodiment ranges from approximately 5 degrees to 60 degrees, more specifically about 45 degrees is preferred. Key **5160** makes an angle of key angle **5275** in one embodiment with respect to horizontal line **5280**. Key angle **5275** ranges from approximately 5 degrees to 60 degrees, more specifically about 45 degrees is preferred, but in any case substantially equal to lock angle **5285**. Methods of cutting lock **5150** and key **5160** (e.g. using saw blades, high speed molders, abrasive grinding tools, or a router fitted with cutting tools for FC materials) are well known in the art.

FIG. **22** shows a cross-sectional view of two installed plank assemblies. As shown in FIG. **22**, a first nail **5340** rigidly attaches a first plank assembly **5300** to a mounting surface **5360**. Mounting surface **5360** is typically a wall stud. A second nail **5350** rigidly attaches a second plank assembly **5310** to mounting surface **5360**. First plank assembly **5300** and second plank assembly **5310** are substantially identical to plank assembly **5100** previously described. First plank assembly **5300** includes key **5320**, which is inserted into lock **5330** of second plank assembly **5310**.

FIG. **23** shows a method of installing plank assemblies onto a mounting surface, including the following steps:

Step **5410**: Mounting first plank assembly. In this step, first plank assembly **5300** is placed against mounting surface **5360** as shown in FIG. **22**. First nail **5340** is driven into first plank assembly **5300** to rigidly attach it to mounting surface **5360**.

Step **5420**: Aligning lock and key features. In this step, second plank assembly **5310** is placed against mounting surface **5360** above first plank assembly **5300** such that lock **5330** of second plank assembly **5310** is aligned with key **5320** of first plank assembly **5300**, as shown in FIG. **22**.

Step **5430**: Lowering second plank assembly. In this step, second plank assembly **5310** is lowered onto first plank assembly **5300**. As plank assembly **5310** is lowered (with the help of gravity) onto first plank assembly **5300**, key **5320** of first plank assembly **5300** automatically engages and aligns lock **5330** of second plank assembly **5310** into a locked position. In this locked position, key **5320** of first plank assembly **5300** prevents second plank assembly **5310** from moving under the influence of wind forces, and therefore prevents wind-induced damage.

Step **5440**: Mounting second plank assembly. In this step, second nail **5350** is driven into second plank assembly **5310** to rigidly attach it to mounting surface **5360**.

Advantageously, the siding plank assembly of this assembly can be used to mate two siding planks tightly and uniformly without requiring a visible nail fastening the overlapping region of the two planks to resist high wind loads. Furthermore, the siding plank assembly requires no starter strip at the base of the wall to provide the lap plank angle of the first installed plank. The lock and key also set the horizontal gauge of the exposed plank face without requiring frequent measuring.

It will be appreciated that another way to prevent wind forces from damaging planks is to nail the butt piece down. However, this method is time extensive, may cause breaks or splits in the FC material, and reduces the aesthetic appeal of the installed plank.

B. Plank Having Oversized “V” Style Lock and Compressible Regions, and Method of Making Same

In another embodiment, a two-piece FC plank utilizes an oversized “V” style lock system and added compressible material to provide added ease of installation and aesthetic value. This embodiment also applies to any plank of similar shape that uses a locking mechanism in place of face nailing an outer plank bottom edge to an inner plank top edge, where the inner plank top edge has been nailed to a frame. The “V” style lock allows planks to be locked into one another without requiring extensive measurement to maintain gauge (the visible vertical distance between planks) and overlap (the vertical distance the plank overhangs the plank below) during installation.

The design described below is particularly advantageous for walls that are not completely planar. When installing exterior siding, it is common to encounter walls that are not completely planar. For example, wood studs within a wall may bow when the wood dries after installation and create a non-planar or “wavy” wall. This presents both installation problems and finishing issues. If a “V” style FC plank does not lock completely (such that both planks being locked are flat against the wall), the gauge and overlap vary across the wall. As a result of being poorly fitted, the plank may subsequently experience lateral movement (flapping) when subjected to wind.

Advantageously, the planks described herein are more easily installed on non-planar walls because they can fit together without excessive force. Furthermore, the lock and key design will maintain gauge and overlap better than other “V” style lock designs. As such, the planks will look better on the wall because they will be straighter than the frame, which is often non-planar.

FIG. 24 shows an isometric view of a FC plank assembly 6100, which includes a plank body 6105, a lock assembly 6150, and an adhesive 6115. Plank body 6105 is fixedly connected to lock assembly 6150 via an adhesive layer 6115, as shown in FIG. 24. Adhesive 6115 is preferably a polymeric hot-melt adhesive or a cementitious adhesive. The method of making a two-piece plank bonded with one of these two adhesives is described above. Table 3 shows preferred ranges of plank body 6105 dimensions for one embodiment:

TABLE 3

Preferred range of plank dimensions	
Dimension	Range/Units
Thickness	about 3/16-1/2 inch
Width	about 5-12 inches
Length	about 12-16 feet

FIG. 25 shows a cross-section of plank assembly 6100 taken along line 25-25 shown in FIG. 24. This view shows how lock front surface 6370 is bonded to plank back surface 6120 via adhesive 6115. The method used to bond lock front surface 6370 to plank back surface 6120 is the same as that described above. FIG. 26 shows a key 6200, part of plank assembly 6100, in greater detail. Key 6200 includes key tip 6210, which is a surface cut on a horizontal plane, parallel to horizontal line 6212, to “blunt” the edge between plank front surface 6215 and plank top surface 6110. The length of key tip 6210 is  $X_k$ , as shown in FIG. 26. Length  $X_k$  may vary in one embodiment from about 1/16" to 3/16". Plank top surface 6110 is cut at an angle  $\theta$ , relative to horizontal line 6212, which may range from about 5 degrees to 60 degrees.

FIG. 27 shows the lock assembly 6150 in greater detail, including a lock inner angled surface 6315, where first compressible region 6310 is located, a lock inner surface 6325, where second compressible region 6320 is located, and a lock inner blunted surface 6330. The length of lock inner blunted surface 6330 is  $X_1$ , as shown in FIG. 27. Length  $X_1$  may range from about  $X_k + 1/16"$  to  $X_k + 1/8"$ . First compressible region 6310 and second compressible region 6320 may be constructed of compressible materials, such as polyurethane elastomeric foam, rubber, rubber foam, or silicone rubber.

Again in reference to FIG. 27, lock inner blunted surface 6330 is shown at an about 90-degree angle to lock front surface 6370. The purpose of “blunting” the sharp cut where lock inner surface 6325 and lock inner angled surface 6315 meet is to provide a substantially flat surface rather than a sliding point for the plank assembly to be locked into the plank assembly above. Lock inner blunted surface 6330 provides a more positive gauge for the plank assembly.

FIG. 28 shows the approximate dimensions of lock assembly 6150. Preferred ranges for the labeled dimensions in FIG. 27 and FIG. 28 are shown below in Table 4.

TABLE 4

Preferred range of variables for lock assembly dimensions as shown in FIGS. 27 through 29	
Dimension as Labeled in FIG. 28 and FIG. 29	Range of Dimension
A	about 3/16" to 1/2"
B	about 3/16 to 1/2"
C	about 0" to 1 1/4"
D	about 1/2" to 2.0"
H	about 1/2" to 2.0"
W	about 3/8" to 3/4"
$X_k$ (key)	about 1/16" to 3/16"
$X_1$ (lock)	about $X_k + 1/16"$ to $X_k + 1/8"$
Y	about 1/32" to 1/8"
$\alpha$ (alpha)	about 0 degrees to 60 degrees
$\beta$ (beta)	about 0 degrees to 30 degrees
$\gamma$ (delta)	about 30 to 85 degrees
$\delta$ (gamma)	about 30 to 85 degrees

FIG. 29 illustrates how key 6200 of a first plank assembly 6510 fits into lock assembly 6150 of a second plank assembly 6520, and how the shape of lock assembly 6150 and key 6200 enhance the performance of the plank assembly. Lock inner blunted surface 6330 and key tip 6210 are each cut at 90-degree angles to plank front surface 6215. This design allows the plank assemblies some lateral compensation for installation on non-planar walls. Although lock assembly 6150 may shift laterally after being installed, the overlap is maintained because key tip 6210 and blunted surface 6330 do not shift vertically. First compressible region 6310 and second compressible region 6320 have been added to the embodiment to



seal lock assembly 6150 with key 6200, and to absorb lateral movement of plank assembly 6510 and 6520. The existence of compressible regions 6310 and 6320 also increases the ease of installation because the plank assemblies can be locked into place without requiring excessive force. The second plank assembly 6520 locked into the first plank assembly 6510 below it can move within the compressible distance between lock inner angled surface 6315 and the top of first compressible region 6310, and between lock inner surface 6325 and the top of second compressible region 6320.

Because the wall frame is often not "plumb" (the wall may be non-planar), the top surface of key 6200 does not form a straight line. By allowing the bottom surface of second plank assembly 6520 to move relative to the key 6200, the lock assembly 6150 can still be straight when placed over the key 6200 (it is being held straight by its own stiffness). Although not perfect, the arrangement is a considerable improvement in the waviness of the wall compared with just following the faults in the frame.

FIG. 30 shows how a siding system 6400 appears after installation on a mounting surface 6410. Mounting surface 6410 is typically made of a series of wall studs (not shown). Plank assemblies 6400A, 6400B, 6400C, and 6400D are installed such that each plank assembly locks into the plank assembly below it. For example, nail 6420A fixes the top of plank assembly 6400A to mounting surface 6410. Plank assembly 6400B is installed directly above it, such that the oversized "V" style lock secures plank assembly 6400B. Nail 6420B then fixes the top of plank assembly 6400B to mounting surface 6410. This process is repeated with plank assembly 6400C, plank assembly 6400D, nail 6420C, and any additional plank assemblies and nails required to cover the mounting surface as desired.

The lock and key design, combined with compressible regions 6310 and 6320, provide some "give" (lateral compensation) in siding system 6400. As a result, the siding will compensate for moderate non-planarity of mounting surface 6410 and siding system 6400 will appear planar (flat).

FIG. 31 shows a flow chart of a method 6500 of making a two-piece FC plank with an oversized "V" style lock and compressible regions, including the steps of:

Step 6510: Manufacturing plank. In this step, a plank is preferably manufactured according to conventional Hatschek methods.

Step 6520: Bonding plank pieces. In this step, plank body 6105 is bonded to lock assembly 6150 to form the plank assembly 6100 shown in FIG. 24. The method of bonding two pieces of FC material to form a two-piece plank either using a polymeric hot-melt adhesive or a cementitious adhesive is described above in greater detail. Some alternate embodiments may not require this step if they do not include bonded pieces.

Step 6530: Machining plank to form key and lock. In this step, planks are fabricated and machined to the requisite shape. In reference to FIGS. 24-26, plank body 6105 is cut to form the plank top surface 6110 and plank bottom surface 6130. Specifically, plank top surface 6110 is cut (to form the key) at an angle of  $\theta$ , which ranges from about 5 degrees to 60 degrees, as shown in FIG. 26. Plank bottom surface 6130 is cut at an angle of  $\beta$ , which ranges from about 0 to 30 degrees, as shown in FIG. 27. To form the lock assembly 6150, the bonded piece is first cut at angle beta to form lock bottom surface 6360, as shown in FIG. 27. The remaining surfaces of lock assembly 6150 are cut to meet the specifications of length and angle listed in Table 4 above. Moreover, this step

uses the same method as described above in making a two-piece plank with a lock and key design, including steps required to cut the plank.

Step 6540: Attaching compressible regions. In this step, first compressible region 6310 and second compressible region 6320 are attached to lock assembly 6150. Materials that may be used for compressible regions 6310 and 6320 include commercially available products such as polyurethane elastomeric foam, rubber, rubber foam, and silicone rubber. The compressible regions are applied using conventional application methods, such as "Nordsons" FoamMelt® application equipment such as the Series 130, applied at about 250 degrees F. to 350 degrees F. First compressible region 6310 is applied to the length of the lock assembly 6150 along lock inner angled surface 6315, and second compressible region 6320 is applied to the length of lock assembly 6150 along lock inner surface 6325, as shown in FIG. 27. The thickness  $y$  of compressible region 6310 and compressible region 6320, as shown in Table 4, may range from about  $\frac{1}{32}$ " to  $\frac{1}{8}$ ".

This particular embodiment describes a two-piece plank; however, the use of compressible regions may be applied to other plank designs as well. Some examples of planks that could utilize this feature are any of the above-described one or two piece planks and the below-described plank having a plastic spline. An extruded plank could utilize this feature, as could any plank of similar shape that uses a locking mechanism in place of face nailing an outer plank bottom edge to an inner plank top edge, where the inner plank top edge has been nailed to a frame. Exemplifying diagrams of two plank designs that could utilize the compressible regions are shown in FIG. 32.

FIGS. 32A and 32B show plank designs that could utilize compressible regions to enhance the plank functionality. FIG. 32A shows extruded plank 6810 with first compressible region 6812A and second compressible region 6814A. FIG. 32B shows hollow plank 6820 with first hollow region 6815 and second hollow region 6817, where the hollow regions may be filled with foam or other material, or left open with no fill, and also shows first compressible region 6812B and second compressible region 6814B.

The design described above advantageously allows planks to be more easily installed on non-planar walls because they can be fit together without excessive force. The compressible material also advantageously forms a capillary break, such as described below. Furthermore, the compressible material acts as a seal against wind and rain.

#### V. Two-Piece Plank Having a Plastic Spline

In additional embodiments, a plastic spline having a butt and lock is provided, which is designed for use in combination with a FC plank for a siding application. The result is a two-piece FC plank assembly having an FC siding plank bonded with an adhesive to a plastic spline having a butt and lock.

Advantageously, the siding assembly of these embodiments provide a lightweight siding assembly having a reduced amount of the FC material while maintaining an aesthetically pleasing shadow line when installed. They also provide for a low-cost siding assembly with increased stiffness and strength, which reduces breakage and improves handleability and ease of installation. The siding assembly is also suitable for blind nailing and capable of high wind loads. The spline can also be easily manufactured from plastic with fine details using an extrusion and or molding processes well known in the art. The term plastic includes, but is not limited to, polymeric resins, copolymers and blends thereof with

suitable flexural and tensile strength for the anticipated use and a heat deflection point well above the maximum normally experienced in the building environment (approximately 40° C. to 60° C.). Such plastics could include but are not limited to: polystyrene, polyvinyl chloride, polyolefin, polyamide (nylon), and ABS. These plastics can contain mineral fillers to reduce cost or weight and improve strength or toughness properties. Alternatively, these plastics may also contain fibers to improve tensile strength. The plastic spline can be manufactured using low grade or recycled plastic for additional cost savings without sacrificing desired attributes.

A. Spline with Angled Lock

FIG. 33 shows an isometric view of the siding plank assembly of one preferred embodiment. Plank assembly 7400 includes a plank 7100 and a spline 7200. Plank 7100 is preferably a siding plank manufactured of medium-density FC material using a well-known Hatschek process. Spline 7200 is a "butt and lock" type spline manufactured of rigid plastic using a well-known extrusion process. Spline 7200 is aligned and is fixedly connected with an adhesive to plank 7100 (described in greater detail below).

FIG. 34 shows an isometric view of the FC siding plank of a preferred embodiment. Plank 7100 is a siding plank that includes a plank top surface 7105, and a plank back surface 7120. Plank 7100 has a length "l", a width "w", a height "h", and a flat "t". An example of plank 7100 dimensions include "l" between about 12 and 16 feet, "w" between about 3/16 and 1/2 inches, "h" between about 5 and 12 inches, and "t" between about 0 and 1/4 inches. A cross-sectional diagram of plank 7100 is shown in FIG. 35.

FIG. 35 is a cross-sectional diagram of plank 7100 taken along line 35-35 of FIG. 34. In this view, additional details of the plank 7100 are visible. Plank 7100 further includes a plank bottom surface 7110 and a plank front surface 7115. Also shown are plank top surface 7105 and plank back surface 7120. Plank top surface 7105 is set at an angle "α" to plank front surface 7115. Plank bottom surface 7110 is set at an angle "β" to plank front surface 7115. In one example, "α" is 45° and "β" is 84°. Angles "α" and "β" of plank 7100 are cut using angled water jet cutters during normal Hatschek manufacturing processing. Preferred dimensions and angles of plank 7100 are indicated in Table 5.

TABLE 5

Plank 7100 dimensions	
Dimension	Range of Dimension
Width "w"	about 0.1875 to 0.500 inches
Height "h"	about 5 to 12 inches
Length "l"	about 12 to 16 feet
Flat "t"	about 0 to 0.250 inches
angle "α"	about 5 to 60 degrees
angle "β"	about 60 to 90 degrees

FIG. 36 shows an isometric view of the plastic locking spline of a preferred embodiment. Spline 7200 includes a generally vertical plate 7205, a plate back surface 7210, a first flange 7215, a first flange top surface 7220, a second flange 7230, a third flange 7240, a third flange top surface 7245, and a fourth flange 7255. Spline 7200 has a length "l", a width "w", and a height "h". An example of spline 7200 dimensions include "l" between about 12 and 16 feet, "w" between about 3/8 and 3/4 inches, and "h" between about 1/2 and 2 inches. A cross-sectional diagram of spline 7200 is shown in FIG. 37.

FIG. 37 is a cross-sectional diagram of spline 7200 taken along line 37-37 of FIG. 36. In this view, additional details of

the spline 7200 are visible. Spline 7200 further includes a first flange bottom surface 7225, a second flange front surface 7235, a third flange bottom surface 7250, and a fourth flange front surface 7260. Also shown is plate 7205, plate back surface 7210, first flange 7215, first flange top surface 7220, second flange 7230, third flange 7240, third flange top surface 7245, and fourth flange 7255.

A first edge of first flange 7215 is integrally connected at an angle to a first edge of elongated plate 7205. A second edge of elongated plate 7205 is integrally connected at an angle along third flange 7240 between the first and second edges of third flange 7240. A first edge of fourth flange 7260 is integrally connected to a second edge of third flange 7240 in parallel with plate 7205. A first edge of second flange 7230 is integrally connected along first flange 7215 between the first and second edges of first flange 7215 in parallel with plate 7205. Second flange 7230 and fourth flange 7260 are coplanar.

FIG. 38 is an end view of spline 7200. Approximate dimensions and angles of a preferred embodiment of spline 7200 are indicated in Table 6.

TABLE 6

Spline 7200 dimensions	
Dimension	Range of Dimension
Width "w"	about 0.375 to 0.750 inches
Height "h"	about 0.500 to 2.0 inches
Length "l" (shown in FIG. 36)	about 12 to 16 feet
"a"	Plank 100 width* - 0.0625 inches
"b"	w - a
"c"	Plank 100 width* - 0.0625 inches
"d"	(h - e) to (0.1 × h)
"e"	(h - d) to (0.1 × h)
"t"	about 0.020 to 0.080 inches
"α"	about 5 to 60 degrees
"β"	about 60 to 90 degrees

\*Plank 100 width = about 0.375 to 0.500 inches

FIG. 39 is a cross-sectional diagram of plank assembly 7400 taken along line 39-39 of FIG. 33. In this view, additional details of the plank assembly 7400 are visible. Plank assembly 7400 further includes a first adhesive layer 7410, a second adhesive layer 7420, and a third adhesive layer 7430. With continuing reference to FIG. 39, the position of spline 7200 is shown in relation to plank 7100. First flange top surface 7220 forms a landing adapted to support a bottom portion of the plank 7100 and is fixedly connected to plank bottom surface 7110 with first adhesive layer 7410. Second flange front surface 7235, which forms part of the landing, is fixedly connected to plank back surface 7120 with second adhesive layer 7420. Fourth flange front surface 7260 is fixedly connected to plank back surface 7120 with third adhesive layer 7430. Third adhesive layer 7430 is formed to direct water away from the joint.

Adhesive layer 7410, 7420 and 7430 is preferably a fast setting, reactive hot-melt polyurethane such as H.B. Fuller 2570x or H.B. Fuller 9570 with a viscosity of about 10,000 to 100,000 CPS at application temperatures ranging from about 200° to 350° F. The adhesion time ranges from about 3 to 5 seconds.

FIG. 40 shows the same details as FIG. 39 with the addition of a chamfer 7450. Chamfer 7450 is placed at an angle "ε" relative to plank front surface 7115 and may be flat or slightly rounded. Angle "ε" is preferably in the range of about 30 to 60 degrees. With continuing reference to FIG. 40, chamfer 7450 is accomplished by cutting or grinding plank 7100, first adhesive 7410 and spline 7200 such that the three elements are "blended". Chamfer 7450 creates a smooth and aesthetically

pleasing drip-edge for plank assembly **7400**, suitable for painting. As chamfer **7450** is exposed to the weather, first adhesive **7410** acts as a seal between plank **7100** and spline **7200**, blocking wind and moisture.

FIG. **41** shows a two-piece siding plank system of a preferred embodiment. Siding system **7500** includes plank assemblies **7400A**, **7400B**, **7400C** and **7400D**, a wall **7510**, and nails **7520A**, **7520B**, and **7520C**. Using a well-known blind nailing technique, plank assemblies **7400A**, **7400B**, **7400C**, and **7400D** are fixedly connected to wall **7510** using nails **7520A**, **7520B**, and **7520C**, respectively (i.e. nails are driven through plank front surface **7115** of plank **7100** (FIG. **35**) in proximity to plank top surface **7105**).

Third flange bottom surface **7250** and plate back surface **7210** of plank assembly **7400B** are positioned in contact with plank top surface **7105** and plank front surface **7115** of plank assembly **7400A**, respectively. Likewise plank assembly **7400C** and **7400D** are positioned in contact with plank assembly **7400B** and **7400C**, respectively.

Another example of this embodiment is a two-piece siding plank assembly with a plastic spline and lock, wherein the plastic spline has one or more dovetail grooves in the first flange top surface, second flange front surface, and fourth flange front surface, with the grooves running along the length of the surfaces, such as described below.

FIG. **42A** shows a cross-sectional view of spline **7200** with the above-mentioned dovetail grooves. The exploded view in FIG. **42B** shows one or more dovetail grooves in first flange top surface **7220**, second flange front surface **7235** and fourth flange front surface **7260** of spline **7200**. The dovetail groove **7220** provides a mechanical bond together with the adhesive bond to plank **7100** of plank assembly **7400** (FIG. **33**). This is illustrated in FIGS. **43A** and **43B**.

FIG. **43A** shows a cross-sectional view of plank assembly **7400**. The exploded view in FIG. **43B** illustrates the interface of spline **7200**, adhesive layer **7410**, **7420** or **7430** and plank **7100**. FIG. **43B** shows adhesive layer **7410**, **7420** or **7430** filling the dovetail grooves of spline **7200**. Due to the dissimilar expansion attributes (temperature and moisture) between plank **7100** and spline **7200**, stresses are induced in adhesive layers **7410**, **7420** and **7430**. In the event that the adhesive bond between the adhesive layers and the plastic spline fails due to these stresses, there is still a mechanical connection by means of the dovetail groove(s).

Another example of this embodiment is a two-piece siding plank assembly using a plastic spline without a lock, without an overlap guide (such as formed by the third flange **7240** of FIG. **36**), and with or without dovetail grooves, as shown in FIGS. **44A** and **44B**. FIGS. **44A** and **44B** show a two-piece siding plank assembly **7600** and siding system **7700**, respectively. Plank **7610** is identical to plank **7100** of FIG. **33** except that plank top surface **7105** (FIG. **35**) is not angled. Spline **7620** is identical to spline **7200** of FIG. **33** except that third flange **7240** (FIG. **36**) is not extended to create the locking mechanism. Siding system **7700** is assembled as described in FIG. **44B** except that the gauge of the plank must be measured during the installation process. This embodiment will create a thick butt (deep shadow line) but does not provide a natural overlap guide for installation.

Another example of this embodiment is a two-piece siding plank assembly using a plastic spline without a lock and with or without dovetail grooves as shown in FIGS. **45A** and **45B**. FIGS. **45A** and **45B** shows a two-piece siding plank assembly **7800** and siding system **7900**, respectively. Plank **7810** is identical to plank **7610** of FIG. **44A**. Spline **7820** is similar to spline **7200** of FIG. **33** except that fourth flange **7255** (FIG. **36**) is eliminated and third flange **7240** (FIG. **36**) is shortened

and angled to about 90°. Siding system **7900** is assembled as described in FIG. **45B**. This embodiment will create a thick butt (deep shadow line) and provide a natural overlap guide for easy installation, but will not handle high wind loads.

Another example of this embodiment is a two-piece plank for a siding application using a natural wood or engineered wood siding plank bonded with an adhesive to a plastic spline with or without a lock.

FIG. **46** shows a flow chart **7950** of the method for making a two-piece plank assembly using an FC siding plank bonded with an adhesive to a plastic spline that involves:

Manufacturing plank **7960**: A plank is formed according to conventional Hatschek methods. The plank top and bottom edges are cut to an angle using angled water jet cutters during the conventional Hatschek manufacturing process. The plank is pre-cured then autoclaved as per conventional methods. See Table 5 for preferred ranges of plank dimensions.

Pre-Treatment of plank & spline **7970**: Plank **7100** and plastic spline **7200** (manufactured according to Table 6) are pre-cut to a desired and equal length. The surfaces of plastic spline **7200** are pre-treated in one of four ways to improve the adhesive bonding capabilities. The four methods of pre-treating the surfaces of the plastic spline are:

Sanding, using conventional power sanding tools;

Cleaning, using a solvent such as Isopropyl Alcohol;

Flame, expose to oxidizing flame fueled by propane gas for about 0.5 to 4 seconds;

A combination of the above.

Bonding plank & spline **7980**: Plank **7100** is bonded to plastic spline **7200** to form the plank assembly **7400** shown in FIG. **33**. Plank **7100** is placed on a first conveyer traveling at a rate up to about 250 feet/minute and three beads of polymeric hot-melt adhesive are applied at a rate of about 1 gram/foot per bead along the length of the plank. The beads are formed so as to align with first flange top surface **7220**, second flange front surface **7235**, and fourth flange front surface **7260** of spline **7200** (FIG. **37**). Spline **7200** is placed on a second conveyer traveling at a rate up to 250 feet/minute. The first and second conveyers feed plank **7100** and spline **7200**, respectively, to a common destination such that the spline aligns to the plank, makes contact with the adhesive, and is fed into a "nip" machine. The rollers of the nip machine are set to the desired overall plank assembly thickness and press plank **7100** and spline **7200** together. The nip machine then feeds the plank assembly **7400** to a press where about 2 to 10 psi of pressure is applied for about 3 to 5 seconds.

Finishing plank assembly **7990**: Plank assembly **7400** is cut to a specified length and chamfer **7450** is applied (FIG. **40**) using conventional cutting or grinding tools.

B. Spline with Square Lock

The embodiments above using a "V" style lock system allow planks to be locked into one another without requiring extensive measurement to maintain gauge (the visible vertical distance between planks) and overlap (the vertical distance the plank overhangs the plank below) during installation. While the "V" style lock design has many inherent advantages, this design does not function satisfactorily for small variations in gauge that are sometimes desired by installers, especially when trying to level-out inaccuracies in framing and installation around window and door openings. As a result of being poorly fitted, the plank may subsequently experience lateral movement (flapping) when subjected to wind. Rather, a lock design that allows for small variations in gauge while preventing lateral movement (flapping) when subjected to wind would be beneficial.

FIG. **47** shows an isometric view of the siding plank assembly of another embodiment of the present invention that

solves these problems. Plank assembly **8400** includes a plank **8100** and a spline **8200**. Plank **8100** is preferably a siding plank manufactured of medium-density FC material using the well-known Hatschek process. Further information regarding the manufacture of plank **8100** may be found in Australian Patent No. AU 515151.

Spline **8200** is preferably a "butt and lock" type spline made of rigid plastic formed by extrusion. Spline **8200** is aligned and is fixedly connected with an adhesive to plank **8100** (described in greater detail below). FIG. **48** shows an isometric view of the FC siding plank of a preferred embodiment. Plank **8100** is a siding plank that includes a plank back surface **8120**, a plank key **8125**, a plank key back surface **8135**, and a nailing region **8145**. Plank **8100** has a length "l", a width "w", and a height "h." An example of plank **8100** dimensions include "l" between about 12 and 16 feet, "w" between about 3/16 and 1/2 inches, and "h" between about 5 and 12 inches. A cross-sectional diagram of plank **8100** is shown in FIG. **49**.

FIG. **49A** is a cross-sectional diagram of plank **8100** taken along line **49-49** of FIG. **48**. In this view, additional details of the plank **8100** are visible. Plank **8100** further includes a plank top surface **8105**, a plank bottom surface **8110**, a plank front surface **8115**, a plank key front surface **8130**, and a bevel edge **8140**. Also shown is plank back surface **8120**, plank key **8125**, plank key back surface **8135**, and nailing region **8145**.

Plank top surface **8105** is set at an angle "d" to plank key front surface **8130**. Angle "d" of plank **8100** is cut using angled water jet cutters during the normal Hatschek manufacturing process. Plank **8100** has a key depth "a," a key height "b," and a nailing region "c."

FIG. **49B** is an exploded view of the plank top surface **8105** taken along line **49B-49B**. In addition to being set at an angle "d" to the plank key front surface **8130**, the plank top surface **8105** has a cant. The cant has a depth "e" from the plank key back surface **8135** and a height "f." Preferred dimensions and angles of plank **8100** are indicated in Table 7.

TABLE 7

Preferred Plank 8100 dimensions	
Dimension	Range of Dimension
Length "l"	about 12 to 16 feet
Width "w"	about 0.1875 to 0.50 inches
Height "h"	about 5 to 12 inches
Key depth "a"	("t" of Table 8) + (about 0.0625 to 0.375) inches
Key height "b"	("d" of Table 8) + about 0.125 inches
Nailing region "c"	about 0.250 to 1.0 inches
Top angle "d"	about 0° to 20°
"e"	about 0.0 to 0.125 inches
"f"	about 0.0 to 0.125 inches

FIG. **50** shows an isometric view of the plastic locking spline of a preferred embodiment. Spline **8200** includes a plate **8205**, a plate back surface **8210**, a first flange **8215**, a first flange top surface **8220**, a second flange **8230**, a third flange **8240**, a fourth flange **8255**, a fifth flange **8265**, and a fifth flange back surface **8275**. Spline **8200** has a length "l," a width "w," and a height "h."

FIG. **51** is a cross-sectional diagram of spline **8200** taken along line **51-51** of FIG. **50**. In this view, additional details of the spline **8200** are visible. Spline **8200** further includes a plate front surface **8212**, a first flange bottom surface **8225**, a second flange front surface **8235**, a third flange top surface **8245**, a third flange bottom surface **8250**, a fourth flange front surface **8260**, and a fifth flange front surface **8270**. Also

shown is plate **8205**, plate back surface **8210**, first flange **8215**, first flange top surface **8220**, second flange **8230**, third flange **8240**, fourth flange **8255**, fifth flange **8265**, and fifth flange back surface **8275**. All elements are present along the entire length of spline **8200** as shown in FIG. **50**.

A first edge of first flange **8215** is integrally connected orthogonal or at an angle to a first edge of plate **8205** extending from plate front surface **8212**. A second edge of plate **8205** is integrally connected at an angle along third flange **8240** between the first and second edges of first flange **8240** extending from third flange bottom surface **8250**. A first edge of fourth flange **8260** is integrally connected to a first edge of third flange **8240** in parallel with plate **8205** extending from third flange bottom surface **8250**. A first edge of second flange **8230** is integrally connected orthogonal or at an angle along first flange **8215** between the first and second edges of first flange **8215** in parallel with plate **8205** extending from first flange top surface **8220**. Second flange **8230** and fourth flange **8260** are coplanar. A first edge of fifth flange **8265** is integrally connected to a second edge of third flange **8240** in parallel with plate **8205** extending from third flange bottom surface **8250**.

FIG. **52** is an end view of spline **8200**. Preferred dimensions and angles of spline **8200** are indicated in Table 8 below.

TABLE 8

Preferred Spline 8200 dimensions	
Dimension	Range of Dimension
Length "l" (not shown)	about 12 to 16 feet
Width "w"	about 0.375 to 0.750 inches
Height "h"	about 0.500 to 2.0 inches
Thickness "t"	about 0.020 to 0.080 inches
"a"	Plank 8100 width* - about 0.0625 inches
"b"	w - a
"c"	Plank 8100 width* + (about 0.0 to 0.040) inches
"d"	about 0.250 to 1.50 inches
"e"	(h - f) to (0.1 x h)
"f"	(h - e) to (0.1 x h)
"g"	about 0° to 20°
"k"	about 90° to 120°

\*Plank 8100 width = about 0.375 to 0.500 inches

There is no gap if h=e+f. The gap is provided to save material and to eliminate the need for an extrusion mandrel to form the hollow, thereby simplifying the manufacturing process.

FIG. **53** is a cross-sectional diagram of plank assembly **8400** of FIG. **47**. In this view, additional details of the plank assembly **8400** are visible. Plank assembly **8400** further includes a first adhesive layer **8410**, a second adhesive layer **8420**, and a third adhesive layer **8430**. With continuing reference to FIG. **53**, the position of spline **8200** is shown in relation to plank **8100**. First flange top surface **8220** is fixedly connected to plank bottom surface **8110** with first adhesive layer **8410**. Second flange front surface **8235** is fixedly connected to plank back surface **8120** with second adhesive layer **8420**. Fourth flange front surface **8260** is fixedly connected to plank back surface **8120** with third adhesive layer **8430**.

Adhesive layers **8410**, **8420** and **8430** are preferably fast setting, reactive hot-melt polyurethane such as H.B. Fuller 2570, H.B. Fuller 9570, or PURMELT R-382-22 with a viscosity of about 10,000 to 100,000 CPS at application temperatures ranging from about 200° to 350° F. The adhesion time preferably ranges from about 3 to 5 seconds. FIG. **54** shows the same details as FIG. **53** with the addition of a chamfer **8450**. Chamfer **8450** is placed at an angle "ε" relative

to plank front surface **8115** and may be flat or slightly rounded. Angle “ $\epsilon$ ” is in the range of about 15° to 85°. One example of angle “ $\epsilon$ ” is about 45°.

With continuing reference to FIG. **54**, chamfer **8450** is accomplished by cutting or grinding plank **8100**, first adhesive **8410** and spline **8200** such that the three elements are “blended”. Chamfer **8450** creates a smooth and aesthetically pleasing drip-edge for plank assembly **8400**, suitable for painting. As chamfer **8450** is exposed to the weather, first adhesive **8410** acts as a seal between plank **8100** and spline **8200**, blocking wind and moisture.

FIG. **55** shows a two-piece siding plank system of a preferred embodiment. Siding system **8500** includes a plank assembly **8400A** and **8400B**, a wall **8510**, a wall outer surface **8515**, and a nail **8520**. Plank assembly **8400A** includes a plank **8100A** and a spline (that is not shown). Plank assembly **8400B** includes a plank **8100B** and a spline **8200B**.

Using a blind nailing technique, plank assembly **8400A** is fixedly connected to wall **8510** by driving nail **8520** through plank front surface **8115** of plank **8100** (FIG. **54**) in nailing region **8145** located just below the area of plank key **8125** (FIG. **49A**). Plate back surface **8210** (FIG. **50**) of spline **8200B** is in contact with plank key front surface **8130** (FIG. **49A**) of plank **8100A**. Fifth flange front surface **8270** (FIG. **51**) of spline **8200B** is in contact with plank key back surface **8135** (FIG. **48**) of plank **8100A**. A small gap in the range of about 0.0 to 0.125 inches is present between fifth flange back surface **8275** (FIG. **51**) of spline **8200B** and wall outer surface **8515**. Bevel edge **8140** (FIG. **49A**) of each plank assembly allows for easy installation of one plank assembly to another.

If plank assembly **8400A** and **8400B** of siding system **8500** is tightly fit, third flange bottom surface **8250** (FIG. **51**) of spline **8200B** is in contact with plank top surface **8105** (FIG. **49A**) of plank **8100A**. However, in the case where plank assembly **8400A** and **8400B** of siding system **8500** is loosely fit, third flange bottom surface **8250** (FIG. **51**) of spline **8200B** is not in contact with plank top surface **8105** (FIG. **49A**) of plank **8100A** leaving a gap “y” in the range preferably of about 0.0 to 0.25 inches. Gap “y” allows easy leveling of the plank assemblies during installation. In either a tightly or loosely fit siding system the plastic spline of the preferred embodiment prevents lateral movement of plank assembly **8400** when installed.

Another example of this embodiment is a two-piece siding plank assembly with a plastic spline and square lock, wherein the plastic spline has one or more dovetail grooves in the second plate top surface and third plate front surface, with the grooves running along the length of the surfaces as described above in greater detail.

Another example of this embodiment is a two-piece siding plank assembly with a plastic spline and square lock, wherein the plastic spline has a capillary break in the first plate back surface running along the length of the surface as described below in greater detail.

Another example of this embodiment is a two-piece siding plank assembly with a plastic spline and square lock, wherein the siding plank is made of any suitable material including but not limited to wood, engineered wood, or composite wood plastic.

Another example of this embodiment is a one-piece molded or extruded siding plank having a similar cross-sectional shape and providing the same functions as the two-piece siding plank assembly of the first embodiment. In this example, a one-piece siding plank is formed using conventional co-extrusion method or a variable composition fibrous cementitious structural product formed by co-extrusion.

Another example of this embodiment is a one-piece siding plank having a similar cross-sectional shape and providing the same functions as the two-piece siding plank assembly of the previous embodiment. In this embodiment a one-piece siding plank is formed using Applicant’s skin and core technology, as described in pending U.S. application Ser. No. 09/973,844, filed Oct. 9, 2001, the entirety of which is hereby incorporated by reference.

FIG. **56** shows a method for making a two-piece plank assembly using a FC siding plank bonded with an adhesive to a plastic spline, which involves:

Manufacturing plank **8960**: A medium-density plank is prepared according to conventional Hatschek methods. Plank key **8125** and nailing region **8145** of plank **8100** (FIG. **48**) are formed by placing a sleeve of a profiled, offset thickness equal to key depth “a,” on the size roller of the Hatschek machine for a distance equal to key height “b” and nailing region “c.” As a result, the FC green sheet rides on the sleeve creating the offset of plank key **8125** and nailing region **8145**. Alternately, plank key **8125** and nailing region **8145** are formed by profiled press-rollers, where about 200 to 500 psi of pressure is applied to shape these regions. The plank top and bottom edges are cut using angled water jet cutters during the conventional Hatschek manufacturing process. The plank is pre-cured then autoclaved as per conventional methods. See Table 7 above for acceptable ranges of plank dimensions for this embodiment.

Pre-Treatment of plank & spline **8970**: Plank **8100** and spline **8200** (manufactured as per Table 8) are pre-cut to a desired and equal length as shown in FIGS. **49A** and **50**, respectively. The surfaces of plastic spline **8200** (i.e. first flange top surface **8220**, second flange front surface **8235**, and fourth flange front surface **8260**) are pre-treated in one of four ways to improve the adhesive bonding capabilities. The four methods of pre-treating the surfaces of the plastic spline are:

1. Sanding, using conventional power sanding tools to roughen the surface;
2. Cleaning, using a solvent such as Isopropyl Alcohol;
3. Flame, expose to oxidizing flame fueled by propane gas for about 0.5 to 4 seconds;
4. A combination of the above.

Bonding plank & spline **8980**: Plank **8100** is bonded to plastic spline **8200** to form the plank assembly **8400** shown in FIG. **47**. Plank **8100** is placed on a first conveyer traveling at a rate up to 250 feet/minute and three beads of polymeric hot-melt adhesive with a viscosity of about 10,000 to 100,000 CPS at application temperatures ranging from about 200° to 350° F. are applied at a rate of about 1 gram/foot per bead along the length of the plank. The beads are formed so as to align with first flange top surface **8220**, second flange front surface **8235**, and fourth flange front surface **8260** of spline **8200** (FIG. **51**). Likewise, spline **8200** is placed on a second conveyer traveling at a rate equal to the first conveyer. The first and second conveyers feed plank **8100** and spline **8200**, respectively, to a common destination such that the spline **8200** aligns to plank **8100**, makes contact with the adhesive and is fed into a “nip” machine. The rollers of the nip machine are set to the desired overall plank assembly thickness and press plank **8100** and spline **8200** together. The nip machine then feeds the plank assembly **8400** to a press where about 10 to 100 psi of pressure is applied for about 3 to 5 seconds.

Finishing plank assembly **8990**: Plank assembly **8400** is cut to a specified length and chamfer **8450** is applied (FIG. **54**) using conventional cutting or grinding tools.

Advantageously, the siding plank assembly of this embodiment allows for small variations in the siding installed while reducing lateral movement (flapping) when subjected to

wind. The assembly also allows for leveling of the planks during installation and can be formed without machining the lock and key. The locking system allows for easy installation and the plank top surface angle does not need to match the spline fourth plate angle.

### C. Apparatus for Reducing Capillary Action Between Planks

In another embodiment, an apparatus for reducing capillary action is provided in the overlap region between two medium-density FC or other siding assemblies when installed. One example is a plastic spline having a capillary break formed by adding a lip along the length of the spline as described below.

Conventional exterior siding systems also include a "rain screen," which is the combination of an airtight and watertight barrier placed over the exterior surface of the frame to be sided, combined with the siding. The functional purpose of the siding is to keep moisture away from the rain screen inner barrier surface. The siding of FC material, wood or vinyl rain screen is a series of horizontal "planks" which overlap at their upper edges to prevent wind and rain from penetrating to the interior of the rain screen. The rain screen siding system, if properly installed, is very effective at keeping the framing and insulation of the wall dry and airtight under all weather conditions.

When siding planks are installed on an exterior wall of a building, moisture can find its way into the tight space where adjacent siding planks overlap. While most moisture does not enter because of gravity, the width of the gap in the overlap region is usually small enough that capillary action can occur, allowing moisture to penetrate to the internal barrier of the rain screen or at least into the space between the exterior barrier and the siding planks. As a result, the lapped siding material is not completely effective as a water barrier.

While increasing the gap between the siding materials when installed reduces the effect of capillary action, the siding becomes more susceptible to wind driven moisture penetration. Therefore, a siding assembly when installed that prevents water penetration due to rain and capillary action while preventing wind driven penetration would be beneficial. What is needed is a design of lap siding that forms a capillary break to stop the rise of water between the two surfaces in the plank overlap region.

Advantageously, the siding plank assembly of this embodiment reduces capillary action in the siding, thus providing additional moisture protection to the exterior barrier wall and siding interior while maintaining good resistance to wind driven moisture penetration. Furthermore, the assembly keeps the region that is nailed relatively dry, which increases the strength of fiber cement and therefore resistance to dislodgment of the planks by high winds. Another way to solve the problem is to seal the space between the planks with caulk or other type of sealant. However, this adds complexity to the exterior wall system. Alternatively, a gap or groove the length of the plank can be machined in the overlap area. However, this would create a weak point in the plank and would add a manufacturing process step.

FIG. 57 shows an isometric view of the siding plank assembly comprising a two-piece plank having a plastic spline with an angled lock as described above. Plank assembly 9400 includes a plank 9100 and a spline 9200. Plank 9100 is preferably a siding plank manufactured of medium-density FC material using a well-known Hatschek process. Spline 9200 is a "butt and lock" type spline manufactured of rigid plastic using a well-known extrusion process described above. Spline 9200 is aligned and is fixedly connected with an adhesive to plank 9100 as described above. As shown in FIG. 57,

spline 9200 of this embodiment further includes a capillary break 9265 running along the length of spline 9200.

FIG. 58 shows an isometric view of the plastic spline with the capillary break of the preferred embodiment. Spline 9200 includes a plate 9205, a plate back surface 9210, a first flange 9215, a second flange 9230, a third flange 9240, and a fourth flange 9255. Also shown is capillary break 9265 in the form of a lip running along the length of plate back surface 9210 along the lower edge.

Spline 9200 has a length "l", a width "w", and a height "h". An example of spline 9200 dimensions include "l" between about 12 and 16 feet, "w" between about 3/8 and 3/4 inches, and "h" between about 1/2 and 2 inches. A cross-sectional diagram and an end view of spline 9200 are shown in FIGS. 59 and 60, respectively.

FIG. 59 is a cross-sectional diagram of spline 9200 taken along line 59-59 of FIG. 58. Spline 9200 further includes a third flange bottom surface 9250. Also shown is plate 9205, plate back surface 9210, first flange 9215, second flange 9230, third flange 9240, fourth flange 9255, and capillary break 9265.

A first edge of first flange 9215 is integrally connected at an angle to a first edge of elongated plate 9205. A second edge of elongated plate 9205 is integrally connected at an angle along third flange 9240 between the first and second edges of third flange 9240. A first edge of fourth flange 9255 is integrally connected to a second edge of third flange 9240 in parallel with plate 9205. A first edge of second flange 9230 is integrally connected along first flange 9215 between the first and second edges of first flange 9215 in parallel with plate 9205. Second flange 9230 and fourth flange 9255 are coplanar. Furthermore, material is added such that the first edge of first flange 9215 is extended and is not coplanar with plate back surface 9210, thus forming capillary break 9265.

FIG. 60 is an end view of spline 9200 showing approximate dimensions. Preferred dimensions and angles of spline 9200 are indicated in Table 9 below.

TABLE 9

Preferred Spline 9200 dimensions	
Dimension	Range of Dimension
"w"	about 0.375 to 0.750 inches
"a"	Plank 9100 width* - about 0.0625 inches
"b"	w - a
"c"	Plank 9100 width* - about 0.0625 inches
"d"	(h - e) to 0.1*h
"e"	(h - d) to 0.1*h
"f"	greater than about 0.100 inches
"h"	about 0.500 to 2.0 inches
"l" (not shown)	about 12 to 16 feet
"t"	about 0.020 to 0.080 inches
"α"	about 0 to 60 degrees
"β"	about 90 to 60 degrees

\*Plank 9100 width = about 0.375 to 0.500 inches

Note:

if h = d + e there is no gap. The gap is provided to save material.

FIG. 61 shows a two-piece siding plank system as described above. Siding system 9500 includes plank assemblies 9400A and 9400B. Plank assembly 9400B is positioned in contact with plank assembly 9400A. More specifically, third flange bottom surface 9250 (FIG. 59) contacts the top of plank assembly 9400A and capillary break 9265 is in contact with plank front surface 9115 of plank assembly 9400A. The result is a gap located above capillary break 9265 between plate back surface 9210 of plank assembly 9400B and plank

front surface 9115 of plank assembly 9400A. The resulting gap is equal to dimension "f" of spline 9200 running along the length of siding system 9500.

Capillary break 9265 of this embodiment provides a gap equal to dimension "f" of spline 9200 preventing capillary action between plank assemblies 9400A and 9400B. At the same time, capillary break 9265 of a preferred embodiment maintains a wind barrier between plank assemblies 9400A and 9400B, as capillary break 9265 is in direct contact to plank front surface 9115, and third flange bottom surface 9250 (FIG. 59) contacts the top of plank assembly 9400A.

Another example of this embodiment, shown in FIG. 62, is a plastic spline having a capillary break formed by adding a groove along the length of the spline as described below. As this spline is extruded, the wall thickness is kept constant, and the capillary break is formed by a semicircular indentation in the back surface of the plate and a semicircular protrusion in the front surface of the plate.

FIG. 62 shows an isometric view of the plastic spline with capillary break of this embodiment. Spline 9300 includes a plate 9305, a plate back surface 9310, a first flange 9315, a second flange 9330, a third flange 9340, and a fourth flange 9355. Also shown is capillary break 9365 in the form of a groove running along the length of plate back surface 9310. Spline 9300 has a length "l", a width "w", and a height "h". An example of spline 9300 dimensions include "l" between about 12 and 16 feet, "w" between about 3/8 and 3/4 inches, and "h" between about 1/2 and 2 inches. A cross-sectional diagram and an end view of spline 9300 are shown in FIGS. 63 and 64, respectively.

FIG. 63 is a cross-sectional diagram of spline 9300 taken along line 63-63 of FIG. 62. Spline 9300 further includes a third flange bottom surface 9350 and a plate front surface 9370. Also shown is plate 9305, plate back surface 9310, first flange 9315, second flange 9330, third flange 9340, fourth flange 9355 and capillary break 9365. First edge of first flange 9315 is integrally connected at an angle to a first edge of elongated plate 9305. A second edge of elongated plate 9305 is integrally connected at an angle along third flange 9340 between the first and second edges of third flange 9340. A first edge of fourth flange 9360 is integrally connected to a second edge of third flange 9340 in parallel with plate 9305. A first edge of second flange 9330 is integrally connected along first flange 9315 between the first and second edges of first flange 9315 in parallel with plate 9305. Second flange 9330 and fourth flange 9360 are coplanar. Along the length of plate 9305, between the first and second edge of plate 9305, material is indented in a semicircular fashion along the length of plate back surface 9310 and material is similarly protruding along the length of plate front surface 9370, thus forming capillary break 9365.

FIG. 64 is an end view of spline 9300. Preferred dimensions and angles of spline 9300 are indicated in Table 10 below.

TABLE 10

Preferred Spline 9300 dimensions	
Dimension	Range of Dimension
"w"	about 0.375 to 0.750 inches
"a"	Plank 9100 width* - about 0.0625 inches
"b"	w - a
"c"	Plank 9100 width* - about 0.0625 inches
"d"	(h - e) to 0.1*h inches
"e"	(h - d) to 0.1*h inches
"f"	greater than about 0.1 inches

TABLE 10-continued

Preferred Spline 9300 dimensions	
Dimension	Range of Dimension
"g"	greater than about 0.2 inches
"h"	about 0.500 to 2.0 inches
"j"	about 0.250 to 1.0 inches
"l" (not shown)	about 12 to 16 feet
"t"	about 0.020 to 0.080 inches
"α"	about 0 to 60 degree
"β"	about 90 to 60 degree

\*Plank 9100 width = about 0.375 to 0.500 inches

FIG. 65 shows a two-piece siding plank system of a preferred embodiment. Siding system 9600 includes plank assemblies 9400C and 9400D. Plank assembly 9400D is positioned in contact with plank assembly 9400C. More specifically, third flange bottom surface 9350 (FIG. 63) contacts the top of plank assembly 9400C and plate back surface 9310 (FIG. 63) is in contact with plank front surface 9115 (FIG. 61) of plank assembly 9400C. The result is a gap created by the presence of capillary break 9365 between plate back surface 9310 of plank assembly 9400D and plank front surface 9115 of plank assembly 9400C. The resulting gap running along the length of siding system 9600 has a depth substantially equal to dimension "f" of spline 9300 and a width substantially equal to dimension "g" of spline 9300.

Capillary break 9365 of this embodiment provides a gap equal to dimension "f" of spline 9300 preventing capillary action between plank assemblies 9400C and 9400D. At the same time, capillary break 9365 of the present invention maintains a wind barrier between plank assemblies 9400C and 9400D, as plate back surface 9310 is in direct contact to plank front surface 9115.

VI. Fiber Cement Articles with Localized Reinforcement and a Method for Making Same

In additional embodiments, fiber cement articles having localized reinforcements are provided, which is designed in one embodiment for use in combination with a system of FC planks for siding applications. The result is a locally reinforced FC plank assembly having fiber cement articles with localized reinforcements for improving the strength of individual FC siding planks.

Advantageously, the siding plank assembly of these embodiments provide a lightweight siding assembly having a reduced amount of FC material without compromising the strength of the plank. The addition of localized reinforcement provides for a low-cost siding assembly with increased stiffness and strength, which reduces breakage and improves handleability and ease of installation. The siding assembly is also suitable for blind nailing and capable of high wind loads.

FIG. 66 shows a cross-sectional view of a reinforced fiber cement article 10000, which includes a fiber cement article 11000, a reinforcing fixture 13000, and a high-shear adhesive layer 12000 that is situated between fiber cement article 11000 and reinforcing fixture 13000. High-shear adhesive layer 12000 and reinforcing fixture 13000 can be applied to one or both faces of fiber cement article 11000.

Fiber cement article 11000 may be made in accordance with the methods described in Australian patent AU 515151, "Fiber Reinforced Cementitious Articles" and in U.S. Pat. No. 6,346,146, the entirety of each of which is hereby incorporated by reference. However, it will be appreciated that fiber cement articles manufactured by other means, including but not limited to the Hatschek process, Bison process, filter

pressing, flow-on process, Mazza process, Magnani process, roll-forming, or extrusion, can be used in this embodiment.

High-shear adhesive layer **12000** is preferably an adhesive with high-shear strength, good alkali resistance, durability in exterior cladding applications and quick setting capabilities. The adhesive also preferably has sufficient working or “open” time to allow sufficient penetration into the fiber cement substrate. The adhesive also preferably maintains its adhesive properties through exposure to many cycles of heat and cold and/or wet and dry. One method of evaluating the suitability of such adhesive is to conduct a “peel test”, well known in the art, in which the percent retention of peel strength is measured after several exposures to wet and dry and/or heat and cold. Preferably, durable high-shear strength adhesives are used, for instance: hot melt polyurethane adhesives such as Henckel Puremelt 243; hot melt polyamide adhesives such as Henckel-Micromelt 6239, 6238, and 6211; and hot melt modified ethylene vinyl acetate (EVA) adhesives such as Reicholdt 2H850.

The preferred options listed above for the high-shear strength adhesive layer **12000** have the additional property of resisting adhesive failure after five wet/dry cycles of soaking in saturated CaO (alkaline) solution at 60° F. or after twenty-five soak/freeze/thaw cycles.

Reinforcing fixture **13000** is preferably made from any common engineering material, preferably with a tensile strength substantially greater than that of fiber cement article **11000**. More preferably, the reinforcing fixture is made of a non-rigid material. Preferred materials for reinforcing fixture **13000** including, but not limited to, metal foils, woven metal meshes, and expanded metal meshes of sufficient shape and dimension to be suitable for the application. Other materials of relatively high tensile strength, such as polymer films or woven and non-woven polymer fabric meshes may also be used.

As shown in FIG. **66**, both durable high-shear adhesive layer **12000** and reinforcing fixture **13000** are placed on one face of fiber cement article **11000** and centered along the length and width of fiber cement article **11000**. When handling reinforced fiber cement article **10000**, tensile stresses created by flexing fiber cement article **11000** are transferred to reinforcing fixture **13000** via high-shear adhesive layer **12000**.

Reinforcing fixture **13000** can be applied to both faces of fiber cement article **11000** or can be applied to more than one area of fiber cement article **11000** with high-shear adhesive layer **12000** in order to accommodate stresses envisioned in the use and application of fiber cement article **11000**.

Reinforcing fixture **13000** and durable high-shear strength adhesive layer **12000** may be applied to fiber cement shapes other than flat planks, including, but not limited to, panels, roofing shakes or shingles, tiles, slate, thick boards, and hollow or solid extruded profiles, in order to provide reinforcement in critical areas. Thus, it will be appreciated that the reinforcing fixtures described herein are not limited to siding planks.

While reinforcing fixture **13000** is illustrated in FIG. **66** as a flat sheet, reinforcing fixture **13000** may also have any three-dimensional shape required to provide sufficient reinforcement to specific areas of fiber cement article **11000** when attached to fiber cement article **11000** with durable high-shear adhesive **12000**. The dimensions and shape of reinforcing fixture **13000** may be determined by analyzing the stresses in fiber cement article **11000** under specific conditions of load using any number of methods known to the art, including finite element analysis.

One means of evaluating the relative stiffness of reinforced fiber cement article **10000** is the “barrel test,” which measures the ability of a plank to be self-supporting when carried parallel to the ground. In the barrel test, a plank is balanced flat upon the circumference of a barrel placed parallel to the ground. If the plank does not break after a predetermined amount of time, the amount of deflection from horizontal is measured in order to compare the relative stiffness of various plank designs and materials. Table 11 illustrates the relative performance in the barrel test of fiber cement planks made according to the embodiments described herein.

TABLE 11

Deflection and breaking behavior of FC planks in the barrel test		
Article	Deflection and breaking behavior (0 min.)	Deflection and breaking behavior (5 min.)
Control:	16"	N/A
$\frac{3}{16}$ " $\times$ $8\frac{1}{4}$ " $\times$ 12 ft. FC plank	50% chance of breaking	
$\frac{3}{16}$ " $\times$ $8\frac{1}{4}$ " $\times$ 12 ft. FC plank	100% chance of breaking	N/A
$\frac{3}{16}$ " $\times$ 6" $\times$ 12 ft. FC plank laminated with a 6" $\times$ 12 ft. steel foil	22" deflection 0% chance of breaking	23" deflection 0% chance of breaking
$\frac{3}{16}$ " $\times$ $8\frac{1}{4}$ " $\times$ 12 ft. FC plank laminated with a 4" $\times$ 4 ft. steel foil	28" deflection 0% chance of breaking	29.5" deflection 0% chance of breaking
$\frac{3}{16}$ " $\times$ $8\frac{1}{4}$ " $\times$ 12 ft. FC plank laminated with a 2" $\times$ 4 ft. steel foil	36" deflection 0% chance of breaking	39.5" deflection 0% chance of breaking

FIGS. **67**, **68**, and **69** below illustrate examples of fiber cement building products incorporating reinforced fiber cement article **10000**.

FIG. **67** shows a front perspective view of a reinforced fiber cement plank with nailing skirt **20000**, including fiber cement article **11000**, high-shear adhesive layer **12000**, and a metal or plastic nailing skirt **23000**. Nailing skirt **23000** functions as reinforcing fixture **13000** in this application and is preferably attached to fiber cement article **11000** in the manner described above with reference to reinforcing fixture **13000**. Nailing skirt **23000** serves as a nailing area for attaching fiber cement article **11000** to the exterior of a building and is of sufficient thickness to support fiber cement article **11000** when so attached. Nailing through nailing skirt **23000** reduces the amount of overlap required between siding planks. The stiffness of nailing skirt **23000** also provides resistance to wind uplift when the plank is blind nailed.

FIG. **68** shows a rear perspective view of a reinforced fiber cement plank with extruded polymer reinforcing strip **30000**, including fiber cement article **11000**, high-shear adhesive layer **12000**, and a three-dimensional reinforcing fixture **33000**. Three-dimensional reinforcing fixture **33000** functions as reinforcing fixture **13000** in this application and is attached to fiber cement article **11000** in the manner described above with reference to reinforcing fixture **13000**. Three-dimensional reinforcing fixture **33000** functions both to stiffen the plank and as a spacer between planks when several planks are installed on a wall. By providing the function of a spacer, the reinforcing fixture **33000** provides an aesthetically pleasing shadow line when several planks are installed on the wall.

FIG. **69** shows a rear perspective view of a multi-lap fiber cement plank **40000**, including two or more fiber cement articles **11000** joined in an overlapping fashion and bonded together with high-shear adhesive layer **12000**.



FIG. 70 shows a method **5000** for making a fiber cement article with a localized reinforcing fixture, which involves:

Designing reinforcing fixture **51000**: Analyze the stresses on the fiber cement article in its intended use to determine the shape, dimension, and appropriate material for the reinforcing fixture. The analysis and design is performed using methods well known in the art, such as classical bending moment analysis or finite element analysis.

Fabricating reinforcing fixture **52000**: Fabricate the reinforcing fixture **13000** using well-known methods appropriate for the design and material generated in step **51000**. For example, if reinforcing fixture **13000** were a metal foil of specific shape, a die would be fabricated using well-known methods to mechanically stamp the shape from a roll of aluminum foil of a specific thickness.

Applying adhesive to article surface **53000**: Form a high-shear strength adhesive layer **12000** of a predetermined thickness by applying a predetermined amount of durable, high-shear strength adhesive to a predetermined location on the surface of fiber cement article **11000**. High-shear strength adhesive layer **12000** is preferably applied at a temperature in the range of about 200° F. to 400° F. such that the viscosity of the adhesive allows sufficient penetration into the fiber cement surface at the application temperature. The durable, high-shear strength adhesive should ideally allow between about 30 and 60 seconds of working (open) time before setting. The adhesive can be applied using any type of commonly used hot melt application equipment, such as a roll coater, curtain coater, or hot glue gun.

Applying adhesive to reinforcing fixture surface **54000**: Form a high-shear strength adhesive layer **12000** of a predetermined thickness (when required to ensure adequate bonding between fiber cement article **11000** and reinforcing fixture **13000**) by applying a predetermined amount of durable, high-shear strength adhesive to a predetermined location on the surface of reinforcing fixture **13000**. The adhesive is preferably applied at a temperature in the range of about 200° F. to 400° F. such that the viscosity of the adhesive allows it to penetrate into fiber cement article **11000** at the application temperature. The durable, high-shear strength adhesive should ideally allow between about 30 and 60 seconds of working (open) time before setting. The adhesive can be applied using any type of commonly used hot melt application equipment, such as a roll coater, curtain coater, or hot glue gun.

Attaching reinforcing fixture to article surface **55000**: Attach a reinforcing fixture **13000** to a fiber cement article **11000** manually or by mechanical means, such that the point of attachment is high-shear adhesive layer **12000** applied in steps **53000** and/or **54000**.

Applying pressure to reinforcing fixture and article **56000**: Apply a uniform pressure to fiber cement article **11000** and reinforcing fixture **13000** in order to bond reinforcing fixture **13000** to fiber cement article **11000**. In the example of reinforced fiber cement plank with nailing skirt **20000**, pressure is applied by passing fiber cement article **11000** and reinforcing fixture **13000** simultaneously through the nip of a pressurized roller such that the roller uniformly exerts three pounds per linear inch (25 pounds across a 8.25 inch plank width). Other mechanical means may be used to apply pressure to assemblies of more complicated shapes.

Setting adhesive **57000**: Hold fiber cement article **11000** and reinforcing fixture **13000** in place for a predetermined amount of time, pressure, and temperature in order to permanently bond them together. The pressure, time, and temperature required are dictated by the properties of the high-shear adhesive used and line speed of the manufacturing process. In

the example of reinforced fiber cement plank with nailing skirt **20000**, hot-melt polyurethane adhesive is applied at 250° F., the components are assembled within 60 seconds, and the plank is instantaneously pressed using a pressurized nip roll.

Removing fiber cement article from press **58000**: Remove finished reinforced fiber cement article **10000** from the press using manual or mechanical means.

The embodiments for localized reinforcement described above advantageously improve the handleability of thin fiber cement planks or other articles by allowing a thin, lightweight plank or article to have the same stiffness as a much thicker, denser plank or article. By using localized reinforcements durably bonded to specific portions of a fiber cement article, the stiffness, bending strength, and/or impact strength of the fiber cement article may be improved, allowing such articles to be used in applications previously unsuitable for fiber cement due to its brittleness. Fiber cement siding planks formed as described above are capable of handling high wind loads when blind nailed, and provide a way to minimize the amount of overlap between fiber cement planks while maintaining a secure attachment. Articles made according to the methods described above also have greater resistance to adhesive failure after exposure to wet/dry cycles, attack by alkaline solutions, or soak/freeze/thaw cycling. Additionally, by using localized reinforcements durably bonded to specific portions of a fiber article, such articles may be designed for a given application using less fiber cement material and/or fiber cement material of a lower density. In the embodiment above using a foil-backed fiber cement planks, such planks are capable of reflecting heat from a building, which keeps the building cooler in hot weather.

In another embodiment, the problem of providing localized reinforcement to fiber cement articles can be solved by embedding the reinforcing fixture within the fiber cement article while the fiber cement article is in the green or plastic state. Preferably, the reinforcing fixture should be chosen to withstand the high temperature of the curing process of the fiber cement article so as not to lose their effectiveness.

#### Conclusions

Certain preferred embodiments of the present invention provide efficient designs for lightweight fiber cement siding plank assemblies having the traditional deep shadow-line. Particularly, the deep shadow line is created without having to machine the siding plank or otherwise remove any siding plank material. Instead, the siding plank is formed by adding material to a thinner starting base siding plank instead of removing material from a thick rectangular section as shown in prior art. Additionally, two pieces of FC material can be bonded solidly and quickly using the adhesive composition of the preferred embodiments. As such, thin and lightweight planks can be used as siding material that produces a thick shadow line.

Furthermore, the siding plank assembly of certain preferred embodiments provide interlocking features that allow the planks to be installed quickly with ease and maintain a constant gauge of plank rows along the length of the siding and between rows of sidings. The siding plank assembly also provides the installation flexibility of variable gauge height. The siding plank assemblies use gravity to help mate two planks tightly and uniformly without face nailing.

Additionally, certain preferred embodiments of the present invention provide for improved handleability and strength of thin fiber cement planks by allowing a thin, lightweight plank to have the same stiffness as a much thicker, denser plank. This is preferably accomplished by reinforcing specific por-

tions of a fiber cement article with reinforcing fixtures. A locally reinforced article has the advantages of producing a low cost article that handles well during installation and under wind loads. The reinforced article also provides a way to minimize the amount of overlap between fiber cement planks while maintaining a secure attachment as well as a way to reflect heat.

Although the foregoing invention has been described in terms of certain preferred embodiments, other embodiments will become apparent to those of ordinary skill in the art, in view of the disclosure herein. Accordingly, the present invention is not intended to be limited by the recitation of preferred embodiments, but is instead intended to be defined solely by reference to the appended claims.

What is claimed is:

1. A reinforced fiber cement article, comprising:
  - a fiber cement article having a front surface, a back surface, a top surface and a top edge and wherein the front surface and the back surface each have a surface area;
  - a substantially planar reinforcing fixture having a bonding portion bonded to a localized region on at least one of the front surface and the back surface at said top surface, said substantially planar reinforcing fixture comprising, an extending portion extending beyond said top edge and configured to receive a fastener for securing said article to a structure, and said substantially planar reinforcing fixture being disposed to reinforce at least one area on the fiber cement article and to improve the strength of the fiber cement article; and
  - a high-shear strength adhesive layer situated between the fiber cement article and the substantially planar reinforcing fixture, wherein the high-shear strength adhesive layer is capable of maintaining the bond between the substantially planar reinforcing fixture and the fiber cement article even after being subjected to five wet/dry cycles of soaking in saturated CaO solution at 60° F.; wherein the surface of the substantially planar reinforcing fixture has an area that is less than the surface area of the at least one of the front surface and the back surface to which the substantially planar reinforcing fixture is bonded.
2. The reinforced article of claim 1, wherein the high-shear strength adhesive layer covers the localized region of the front surface of the fiber cement article for bonding the substantially planar reinforcing fixture to the fiber cement article.
3. The reinforced article of claim 1, wherein the high-shear strength adhesive layer covers the localized region of the front surface and the back surface of the fiber cement article for bonding the substantially planar reinforcing fixture to the front and back surface of the fiber cement article.
4. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture has a tensile strength greater than the fiber cement article.
5. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture is more flexible than the fiber cement article.
6. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture is a metal foil.
7. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture is a woven metal mesh.
8. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture is a polymer film.

9. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture is a nailing skirt for attaching and supporting the fiber cement article to the exterior of a building.

10. The reinforced article of claim 1, wherein the fiber cement article is a flat siding plank.

11. The reinforced article of claim 1, wherein the fiber cement article has a hollow extruded profile.

12. The reinforced article of claim 1, wherein the fiber cement article has a length extending from one end to another end of the article and the substantially planar reinforcing fixture extends along the entire length of the article.

13. The reinforced article of claim 1, wherein the high shear strength adhesive is capable of maintaining the bond between the fiber cement article and the substantially planar reinforcing fixture even after being subjected to twenty-five soak/dry or freeze/thaw cycles.

14. The reinforced article of claim 1, wherein the high shear strength adhesive has a viscosity sufficient to penetrate into the fiber cement article at about 200 to 400° F.

15. The reinforced article of claim 1, wherein the high shear strength adhesive is a hot-melt adhesive.

16. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture is a polymer fabric mesh.

17. The reinforced article of claim 16, wherein the polymer fabric mesh is non-woven.

18. The reinforced article of claim 1, wherein the substantially planar reinforcing fixture has a thickness, width, and length.

19. The reinforced article of claim 18, wherein the length of the substantially planar reinforcing fixture is substantially the same as the length of the fiber cement article.

20. The reinforced article of claim 18, wherein the substantially planar reinforcing fixture is an interlocking member.

21. The reinforced article of claim 20, wherein the interlocking member is a butt piece.

22. The reinforced article of claim 20, wherein the interlocking member is a plastic spline.

23. The reinforced article of claim 18, wherein the thickness of the substantially planar reinforcing fixture is substantially constant along the length and width of the fixture.

24. The reinforced article of claim 1, wherein the fiber cement article is a roofing shake.

25. The reinforced fiber cement article of claim 24, wherein the substantially planar reinforcing fixture is a mesh.

26. The reinforced fiber cement article of claim 25, wherein the mesh is made of a polymer material.

27. The reinforced fiber cement article of claim 1, wherein the fiber cement article has a thickness of less than  $\frac{3}{16}$  of an inch.

28. The reinforced fiber cement article of claim 27, wherein the thickness of the fiber cement article is about  $\frac{3}{16}$  of an inch.

29. The reinforced fiber cement article of claim 1, wherein the substantially planar reinforcing fixture is a mesh.

30. The reinforced fiber cement article of claim 29, wherein the mesh is made of fabric.

31. The reinforced fiber cement article of claim 29, wherein the fiber cement article is selected from the group consisting of a roofing slate and tile.